
- Wholesale trade.
- Wireless facility.
- b. *Prohibited uses*—In addition to those uses disallowed under the provisions of (a)(1) of this section, the following uses are expressly prohibited in a C-1 district:
 - Mobile homes for residential and/or commercial purposes.
- c. *Uses requiring planning approval*—The uses listed below are permitted upon approval of the location and site plan thereof by the zoning and land use commission as being appropriate with regard to transportation and access, water supply, waste disposal, fire and police protection and other public facilities, as not causing undue traffic congestion or creating a traffic hazard and as being in harmony with the orderly and appropriate development of the district in which the use is located:
 - Ambulance service.
 - Armories—military (reserve or national guard).
 - Church, religious assembly, including parish house, community house and educational buildings.
 - Cultural services.
 - Pipeline or electric transmission line (need not be enclosed within structure).
 - Railroad right-of-way, but not including shops, yards and team tracks (need not be enclosed within structure).
- d. *Special exception uses*—The uses listed below are subject to the same approval of location and site plan as uses requiring planning approval; in addition, these uses are declared to possess such characteristics of unique or special form that each specific use shall be considered an individual case and shall be subject to approval of the board of adjustment, in accordance with the provisions of Article IX governing special exceptions:
 - None.

(2) *Building site area*. There is no minimum building site within the C-1 District.

(3) *Building height limit*. Except as provided in Article IV, no structure shall be erected or altered to exceed one hundred (100) feet (may be reduced if fire hazard).

(4) *Yards required*. No yards are required for any buildings in the C-1 District.

(b) **C-2 Districts: General Commercial Districts.** These districts are composed of land and structures used to furnish, in addition to the retail goods and services found in neighborhood districts, such less frequently needed goods as clothing and automobiles and such less frequently needed services as banking and theaters, the wider range of retail goods and services to satisfy all of the household and personal needs of the residents of a group or community of neighborhoods. Usually located on a thoroughfare or near the intersection of two (2) thoroughfares, these districts are large and are within convenient driving distance of the group of neighborhoods they will serve. The district regulations are designed to permit the development of the districts for their purpose and to protect the abutting and surrounding residential areas by requiring certain minimum yard standards to be met, standards that are comparable to those called for in residential districts. It is intended that additional general commercial districts will be created in accordance with the amendment procedure set forth herein, as they are needed to serve groups of new neighborhoods. To insure that such districts are actually developed to supply the business needs of the groups of neighborhoods, the amendment creating the district may set a time limit for its development.

(1) *Permitted uses*. In the C-2 Districts only the following uses are permitted:

- a. *Uses by right*—The uses listed below are permitted subject to the conditions specified:
 - All uses allowed in the C-1 District.
 - Accessory use.
 - Adult nightclub.
 - Adult uses/materials.
 - Agricultural sales and services.
 - Ambulance services.
 - Animal kennels.
 - Animal sales and services (limited).
 - Apartments.
 - Armories—military (reserve or national guard).
 - Automotive sales and rentals.
 - Boarding houses.
 - Campgrounds.
 - Car wash.
 - Clinic, animal.
 - College and university facilities.
 - Concrete statues, handiwork.
 - Congregate housing.
 - Country club.
 - Day care centers, preschools, nursery schools.
 - Dormitory.
 - Exterminating services.
 - Farm equipment sales and service.
 - Flea markets.
 - Fraternity/sorority residence.
 - Funeral home.
 - Garage, public.
 - Garden center.
 - Governmental buildings (local, state, federal).
 - Laundry services, coin-operated.
 - Laundry services, commercial.
 - Marine services, boat sales/service.
 - Marine services, commercial and charter fishing.

- Marine services, retail.
- Marine services, yacht clubs.
- Microbrewery/microdistillery.
- Nursery, plant.
- Nursing home.
- Outdoor general advertising structure (need not be enclosed within structure).
- Public safety services.
- Recreation, commercial outdoor sports.
- Residential/townhouse residential.
- Residential/condominium residential.
- Residential/multiple-family residential.
- Restaurants, drive-in.
- Restaurants, fast food.
- Restaurants, outdoor fast food.
- Schools, public and private secondary educational facilities.
- Schools, vocational-technical, community, trade or industrial.
- Self-storage warehouse containing rented storage spaces with individual unit area not exceeding seven hundred fifty (750) square feet.
- Shopping center, major.
- Stable, private.
- Taxidermy.
- Truck and heavy equipment sales/rental/service.

b. *Uses requiring planning approval*—The uses listed below are permitted upon approval of the location and site plan thereof by the zoning and land use commission as being appropriate with regard to transportation and access, water supply, waste disposal, fire and police protection and other public facilities, as not causing undue traffic congestion or creating a traffic hazard and as being in harmony with the orderly and appropriate development of the district in which the use is located:

- Church, religious assembly, including parish house, community house and educational buildings.
- Pipeline or electric transmission line (need not be enclosed within structure).
- Railroad right-of-way, but not including shops, yards and team tracks (need not be enclosed within structure).
- Revival church (temporary), as a temporary use on a permit issued by the zoning administrator, such permit to be good for a period not exceeding one week and renewable for not more than three (3) such periods.
- Theater, outdoor (need not be enclosed within structure).

c. *Prohibited uses:*

- Commercial—Mobile homes/trailers.
- Residential/mobile home park.
- Residential—Mobile homes/trailers.
- Gambling or gaming establishments.
- d. *Special exception uses*—The uses listed below are subject to the same approval of location and site plan as uses requiring planning approval; in addition, these uses are declared to possess such characteristics of unique or special form that each specific use shall be considered an individual case and shall be subject to approval of the board of adjustment, in accordance with the provisions of Article IX governing special exceptions:
 - Recreation, outdoor entertainment, but not car racing tracks/facilities.
 - Radio and television broadcasting transmitter and studio.
- (2) *Building site area*. There is no minimum building site area required for commercial businesses. For residential uses, the area required will be same as in the R-3 District.
- (3) *Building height limit*. Except as provided in Article IV, no structure shall be erected or altered to exceed thirty-five (35) feet.
- (4) *Yards required*. Except as provided in Article IV, the minimum dimensions of yards for commercial businesses shall be:

Feet

Front yard 25

Side yard 5

Rear yard 20

For residential use, the yards are the same as for the R-3 District.

Exceptions: A rear yard abutting on a public alley or waterway (bayou or drainage servitude) need only be ten (10) feet in depth, and a rear yard abutting on a lot in a residential or C-4 District shall have the same minimum depth as a rear yard required in the abutting district.

- (c) *C-3 Districts: Neighborhood Commercial Districts*. These districts are composed of land and structures occupied by or suitable for furnishing the retail goods, such as groceries and drugs, and the services, such as barbering and shoe repairing, to satisfy the daily household needs of the surrounding residential neighborhoods. Often located on one (1) or more thoroughfares, these districts are small and are within convenient walking distance of most of the areas they will serve. The district regulations are designed to permit the development of the districts for their purpose and to protect the abutting and surrounding residential areas by requiring certain minimum yard and area standards to be met, standards that are comparable to those called for in residential districts. It is intended that additional neighborhood commercial districts will be created in accordance with the amendment procedure set forth herein, as they are needed to serve new residential areas. To insure that such new districts are actually developed to supply the business needs of the neighborhoods, the amendment creating the district may set a time limit for its development.

- (1) *Permitted uses*. In C-3 Districts only the following uses are permitted:

- a. *Uses by right*—The uses listed below are permitted subject to the conditions specified:

- All uses permitted in C-2 Districts, except as prohibited in b. below.

- Accessory use.