



Cheddar's
casual café



PROTOTYPE 92-SL

REV.	DATE	DESCRIPTION
06-21-10		FOR PERMIT

A1-2

1. ALL FLOORING SHALL BE WOOD 2" X STUD FLOORING 1/2" SHEATHING EACH SIDE UNLESS NOTED OTHERWISE
2. ALL DIMENSIONS ON THIS PLAN ARE TO FACE OF WOOD STUD FLOORING UNLESS NOTED OTHERWISE
3. REFER TO SLAB PLAN SHEET A-6 FOR DIMENSIONS LOCAL TO BASE DECKS
4. PROVIDE 4" MINIMUM DRAIN FLOOR SINKS, FLOOR DRAINS, AND CONCRETE CURBS
5. REFER TO A5-3 FOR WALL BASE CONSTRUCTION DETAILS

ON 2 X 4 STUD FRAMING.
RE: INTERIOR ELEVATIONS AND ROOM FINISH
SCHEDULE FOR WALL FINISH MATERIALS

RE: INTERIOR ELEVATIONS AND ROOM FINISH
SCHEDULE FOR WALL FINISH MATERIALS

6) LOW WALL BETWEEN WAITING AREA AND DINING :
1) WAITING AREA SIDE OF WALL - 1/2" PL. WOOD SHEATHING.
(RE: INTERIOR ELEVATIONS AND ROOF FINISH SCHEDULE)
2) DINING ROOM SIDE OF WALL - 1/2" PL. WOOD SHEATHING ON 2 X 6 STUD FRAMING.
(RE: INTERIOR ELEVATIONS AND ROOF FINISH SCHEDULE)

[illegible]

 8" CMU BLOCK WALL
 5 1/2" TALL X 1'-4" WIDE CONCRETE CURB FOR BAR FOOTREST RE: 04/A3-4

CONTROL DIMENSION LINE "X" - EXTERIOR
FACE OF CONCRETE; GRADE BEAM AND
BRICK VENEER

