County Administrator
Kevin McCrary
County Attorney
Andy R. Beaver
County Clerk
Amanda Hannah

BOARD OF COMMISSIONERS

Board of Commissioners
Mike Gordon
Kevin McCrary
Tim Hopkins
James Thomas
Randy Franks

November 04, 2026

HALL RICHARDSON PAVING CONTRACT
ADDENDUM 1

This Addendum has been issued on behalf of the Wayne County Board of Commission. The following information should be considered by prospective bidders in preparation of their proposals and is hereby incorporated into the Proposal Documents. Bidders shall be responsible for acknowledging receipt of this addendum in the Bid Form. Failure to do so will result in the proposal being considered non–responsive.

BID FORM

1. Schedule of Items revised to include line item 4, "402-3100, Recycled asphalt concrete surface 12.5mm Superpave, GP 1 or 2, Including bituminous material, H lime & tack coat, from 165 lb/sy (1.5" thick) 212 tons to **225#/SY (2") 290 Tons**. This matches detail on sheet C9.5.
2. Heavy duty pavement detail is incorrect on sheet C9.5. This should be revised to match line item 6, "6" thick concrete slab (dumpster pad)".
3. Bidders must use the enclosed form. **NO OTHER FORM SHALL BE ACCEPTED.**

Other Questions asked by contractors:

1. **Will the County supply additional fill material?**
   Yes. Should be a surplus onsite, but any additional fill material needed will be supplied by the County.
2. **Who will perform the layout for the rough grading?**
   The County is responsible for the rough grading and should complete it before the Contractor begins work. This work was performed in-house by the County.
3. **What is the target tolerance for rough grading (e.g., ±0.10 feet)?**
   Rough grading should be within ±0.10 feet.
4. **Will the County grade the outfall ditches as part of the rough grading?**
   Yes.
5. **Will the County install the water and sewer utilities?**
   Yes. The utilities have been installed by the County.
6. **Will the Contractor be responsible for testing?**
   Yes.

7. **Will the Contractor be responsible for dressing, fine grading, and finish grading?**
   Yes. The Contractor is responsible for finish grading around pavement, including sidewalks, flumes, and curb-and-gutter areas. The County will install the ditches; however, the Contractor is responsible for finish grading any areas disturbed by the Contractor.

Brandon Purcell, PE
County Engineer
End of ADDENDUM 1