South Carolina Department of Transportation

South Carolina Department of Transportation **10/7/2026**

Call No.: 200 **Letting Date:** November 10, 2026 **Letting Time:** 2:00 pm

SC File NO(S).: 4477570
DBE Goal Percent: 0.00%

PCN: P045299 **Project No.:** P045299
PCN: P045300 **Project No.:** P045300
PCN: P045301 **Project No.:** P045301
PCN: P045302 **Project No.:** P045302

Approx. Length (miles): 8.0800
CO(S).: Union
Completion Date: 6/30/2028 Days

Description: 2027 UNION PAVEMENT IMPROVEMENT

Funding: ST

ITEMS OF WORK INCLUDE THE FOLLOWING:

Description	Quantity	Units
MOBILIZATION	1.000	LS
BONDS AND INSURANCE	1.000	LS
RAILROAD INSURANCE AND FLAGGING NS	1.000	LS
SELECTED CLEARING & GRUBBING	1.000	LS
REMOVAL & DISPOSAL OF EXISTING PAVEMENT	601.500	SY
REMOVAL OF EXIST. GUARDRAIL	1,450.000	LF
UNCLASSIFIED EXCAVATION	2,341.750	CY
BORROW EXCAVATION	1,412.000	CY
STATION GRADING	36.690	STA
EXCAVATION FOR SHOULDER PAVING	158.400	STA
HAULING OF EXCAVATED SHOULDER MATERIAL	158.400	STA
ADDITIONAL ROCK FOR FULL DEPTH RECLAMATION	2,271.000	TON
MAINTENANCE STONE	178.000	TON
CEMENT MODIFIED RECYCLED BASE (10" UNIF)-CURING METHOD B	55,271.000	SY
CEMENT MODIFIED RECYCLED BASE (12" UNIF)-CURING METHOD B	9,061.000	SY
PORTLAND CEMENT FOR CEMENT MODIFIED RECYCLED BASE COURSE	2,161.000	TON
HMA SHOULDER WIDENING COURSE	1,056.000	TON
LIQUID ASPHALT BINDER PG64-22	1,490.622	TON
FULL DEPTH ASPH. PAV. PATCHING 6" UNIF.	2,813.000	SY
FULL DEPTH ASPH. PAV. PATCHING 8" UNIF	25.000	SY
FULL DEPTH ASPH. PAV. PATCHING 10"UNIF	1,900.000	SY
FULL DEPTH ASPH. PAV. PATCHING 12"UNIF	940.000	SY
MILLING EXISTING ASPHALT PAVEMENT 1.75"	3,291.000	SY
MILLING EXISTING ASPHALT PAVEMENT (VARIABLE)	41,091.000	SY
ASPHALT INTERMEDIATE COURSE TYPE B	5,608.416	TON
ASPHALT INTERMEDIATE COURSE TYPE C	4,058.560	TON
ASPHALT SURFACE COURSE TYPE B	5,306.576	TON
ASPHALT SURFACE COURSE TYPE C	8,962.360	TON
DRIVEWAY PAVING-SURFACE TYPE C	1,134.750	TON
ASPHALT SURFACE TREAT (SINGLE TREATMENT)	64,332.000	SY
TRAFFIC CONTROL	1.000	LS

Description	Quantity	Units
PERMANENT CONSTRUCTION SIGNS (GROUND MOUNTED)	2,364.000	SF
PAVEMENT MARKINGS (TEMPORARY PAINT) 24"X36" WHITE TRIANGLE YIELD BAR	70.000	LF
4" WHITE BROKEN LINES -(GAPS EXCLUDED)-FAST DRY PAINT	8,326.000	LF
4" WHITE SOLID LINES (PVT. EDGE LINES)-FAST DRY PAINT	243,137.000	LF
24" WHITE SOLID LINES (STOP/DIAGONAL LINES)-FAST DRY PAINT	1,778.000	LF
WHITE LANE DROP ARROW (LEFT OR RIGHT)-FAST DRY PAINT	6.000	EA
RAILROAD CROSSING SYMBOLS - FAST DRY PAINT	17.000	EA
4" YELLOW BROKEN LINES(GAPS EXC) - FAST DRY PAINT	3,266.000	LF
4"YELLOW SOLID LINE(PVT.EDGE&NO PASSING ZONE)-FAST DRY PAINT	235,163.000	LF
4" WHITE BROKEN LINES(GAPS EXCL.)THERMOPLASTIC- 90 MIL.	3,030.000	LF
4" WHITE SOLID LINES (PVT. EDGE LINES) THERMO.- 90 MIL.	86,249.000	LF
24IN X 36IN WHITE TRIANG. YIELD BAR (GAPS EXC)THERMO-125MIL	26.000	LF
24" WHITE SOLID LINES (STOP/DIAG LINES)-THERMO.-125 MIL	762.000	LF
WHITE WORD MESSAGE "STOP AHEAD" -THERMOPLASTIC - 125 MIL.	1.000	EA
WHITE LANE DROP ARROW(LT.OR RT.)THERMO-125MIL	2.000	EA
RAILROAD CROSSING SYMBOLS - THERMOPLASTIC - 125 MIL.	5.000	EA
4" YELLOW BROKEN LINES(GAPS EXC)THERMOPLASTIC - 90 MIL.	3,006.000	LF
4" YELLOW SOLID LINES(PVT.EDGE LINES) THERMO-90 MIL.	71,134.000	LF
PERMANENT CLEAR PAVEMENT MARKERS- MONO-DIR.- 4"X4"	113.000	EA
PERMANENT YELLOW PAVEMENT MARKERS MONO-DIR.- 4"X 4" PERM. YEL.	100.000	EA
PERMANENT YELLOW PAVEMENT MARKERS BI-DIR.- 4"X4"	738.000	EA
REMOVAL OF PAVEMENT MARKINGS	96.000	LF
MILLED-IN RUMBLE STRIP	17.700	MI
FURNISH & INSTALL 1.0" SCHEDULE 80 PVC CONDUIT	10.000	LF
FURNISH & INSTL NO. 14 COPPER WIRE,1-CONDUCTOR FOR LOOP WIRE	320.000	LF
SAWCUT FOR LOOP DETECTOR	120.000	LF
F&I-12"X12"X12"D.ELEC.FLUSH UNDGRD.ENCLOS-(STR.POLY.CONC.)HD	1.000	EA
TEMPORARY ADJUSTMENT OF TRAFFIC SIGNAL EQUIPMENT	1.000	EA
15" SMOOTH WALL PIPE	112.000	LF
18" SMOOTH WALL PIPE	64.000	LF
24" SMOOTH WALL PIPE	24.000	LF
CLEANING EXISTING PIPE	364.000	LF
CATCH BASIN -TYPE 1 CB - TYPE 1	5.000	EA
CONCRETE COLLAR FOR UP TO 24" PIPE	10.000	EA
ADJUST CATCH BASIN	2.000	EA
CONCRETE SIDEWALK(4" UNIFORM)	136.000	SY
DETECTABLE WARNING MATERIAL	162.500	SF
CONCRETE DRIVEWAY(6" UNIFORM)	106.000	SY
PEDESTRIAN RAMP CONSTRUCTION	325.000	SY
RIP-RAP (CLASS B)	25.800	TON
GEOTEXTILE FOR EROSION CONTROL UNDER RIPRAP(CLASS 2)TYPE B	30.000	SY

Description	Quantity	Units
MT3 LEADING END TREATMENT TL3	8.000	EA
MGS3CS GR COMPRESSED SHOULDER	1,162.500	LF
RESET FENCE	755.000	LF
PERMANENT GRASSING FOR NON-PERMITTED RESURFACING PROJECTS	3.820	ACRE
SEDIMENT TUBES FOR DITCH CHECKS	40.000	LF
SILT FENCE	400.000	LF
REPLACE/REPAIR SILT FENCE	200.000	LF
REMOVAL OF SILT RETAINED BY SILT FENCE	400.000	LF