SITE DEVELOPMENT PLAN
FOR THE
HALL RICHARDS SENIOR CENTER

ENGINEER
MAVERICK ENGINEERING, LLC
205 GENE BLAND ROAD
JESUP, GEORGIA 31545
(912) 256-3704

CONSTRUCTION PLANS SHEET INDEX

SHEET C1.1	– TITLE SHEET
SHEET C1.2	– GENERAL NOTES
SHEET C2.1	– EXISTING CONDITIONS
SHEET C3.1	– STAKING PLAN
SHEET C4.1	– GRADING AND DRAINAGE PLAN
SHEET C5.1	– UTILITY PLAN
~~SHEET C7.1~~	~~– INITIAL ES&PC PLAN~~
~~SHEET C7.2~~	~~– INTERMEDIATE ES&PC PLAN~~
~~SHEET C7.3~~	~~– FINAL ES&PC PLAN~~
~~SHEET C8.1 THRU .2~~	~~– ES&PC NOTES~~
SHEET C9.1 THRU .6	– SITE DETAILS



VICINITY MAP N.T.S.

OWNER
WAYNE COUNTY BOARD OF COMMISSION
341 E. WALNUT ST.
JESUP, GEORGIA 31546
(912) 427-5900

24-HOUR CONTACT
BRANDON PURCELL
(912) 427-5900
brandon.purcell@waynecountyga.us

DRAWING LEGEND

DESCRIPTION	PROPOSED	EXISTING
RIGHT OF WAY	R/W	R/W
EDGE OF PAVEMENT		
DITCH CENTERLINE		
SANITARY SEWER	8"S	
WATER LINE	10"W	10"W
FORCE MAIN	FM	FM
UNDERGROUND GAS LINE	8"G	8"G
CONTOURS	81	81
STORM DRAINAGE PIPE		
ELEVATION	FG:78.15	X 81.90
SILT FENCE NON-SENSITIVE	Sd1-NS	
SILT FENCE SENSITIVE	Sd1-S	
INLET PROTECTION	Sd2-I	
CHECK DAM- HAY BALE	Cd-Hb	
CHECK DAM - RIP RAP	Cd-Rp	
CONSTRUCTION EXIT	Ce	
STORM OUTLET PROTECTION	R	
SILT FENCE		
MULCHING	Ds1	
TEMPORARY GRASSING	Ds2	
PERMANENT GRASSING	Ds3	
FIRE HYDRANT		
SEWER MANHOLE	S	S
WATER VALVE		
DRAINAGE FLOW		
WATER METER		
BENCHMARK		
WELL	W	W
GUY POLE		
IRON PIN	SET I.P.S	FOUND I.P.F
TELEPHONE PEDESTAL		TEL
POWER POLE		

LOCATION: N31° 36' 56.08", W81° 52' 51.21"
TOTAL DISTURBED ACREAGE: 0.99 AC.
TOTAL SITE ACREAGE: 1.0 AC.

GEORGIA811.COM DIAL 811

THIS DRAWING MAY NOT BE REPRODUCED WITHOUT WRITTEN PERMISSION FROM MAVERICK ENGINEERING, LLC

THE CONTRACTOR SHOULD VERIFY ALL LOCATIONS, GRADES, AND DIMENSIONS ILLUSTRATED ON THE PLANS AND WILL REPORT ANY DISCREPANCIES TO MAVERICK ENGINEERING, LLC.

MAVERICK ENGINEERING, LLC.
205 GENE BLAND ROAD | JESUP, GA 31545
phone (912) 256-3704 www.maverickengineeringllc.com

SITE PLAN
HALL RICHARDS
SENIOR CENTER
PARCEL NUMBER: JT-31, JT-32 & JT-33 JESUP, WAYNE COUNTY, GEORGIA

SHEET NAME:
TITTLE
SHEET

REVISIONS:
1.
2.
3.
4.
5.
6.
7.
8.
9.
10.

INITIAL DATE: 4/17/2025
DRAWN BY: BDP
CHECKED BY: BDP
PROJECT #: 2025-01

SHEET NUMBER:
C I.I

Paving Notes

1. All work shall comply with all applicable codes, regulations, and/or local standards imposed by local utility, city, county, and state. It is the contractor's responsibility that all the construction be in accordance with the City of Jesup and GDOT standard details and specifications.
2. Contractor shall comply with all pertinent provisions of the "Manual of Accident Prevention in Construction" issued by AGC of American Inc., and the safety and health regulations for construction issued by the U.S. Department of Labor.
3. Contractor shall provide all necessary barricades, sufficient lights, signs and other traffic control methods as may be necessary for the protection and safety of the public and shall be provided and maintained throughout all construction adjacent to and within all roadways. Contractor shall submit traffic control plan to city for approval.
4. The contractor shall take necessary measures to separate work areas from pedestrian traffic and to insure safe pedestrian passage at all times.
5. All signs, pavement markings, and other traffic control devices shall conform to the Manual of Uniform Traffic Control Devices. A minimum clearance of two feet shall be maintained between the face of curb and any part of a traffic sign or light pole. Contractor shall coordinate installation of all signs, pavement markings, and other traffic control devices with other contractors on signs or light poles.
6. Contractor shall saw-cut to provide smooth transitions at tie-ins to existing edges of pavement and at cold joints of recently paved asphalt.
7. Joints or score marks are to be sharp and clean without showing edges of jointing tool.
8. Contractor shall saw-cut tie-ins at existing curbs as necessary to ensure smooth transitions, contractor shall saw-cut and transition to meet existing pavement as necessary and as directed by inspector to insure positive drainage. (Typical at all intersections)
9. Paving contractor shall install paper breakaway edges at cold joints or saw-cut as required to insure a straight, full-depth joint face immediately prior to installing abutting hot asphalt.
10. All dimensions are to back of curb unless indicated otherwise.
11. Contractor shall be responsible for cost of pavement replacement where utility lines are extended across existing asphalt.
12. Asphalt surface course shall be laid with the direction of traffic in all drive lanes within parking fields.
13. Base and asphalt thickness are minimum required. Refer to specifications for type of paving and base to be used.
14. All concrete shall be Class A 4000 P.S.I. unless noted otherwise. Do not pour any concrete before forms are inspected and approved by the Inspector.
15. All ramps constructed are not to exceed a slope of 1:12. All sidewalks shall not have a cross-slope greater than 1:50
16. Concrete dumpster pads to be flush with pavement unless indicated otherwise.
17. See Detail sheets for additional details on striping, signs, etc.

Inspection notes

1. Each day when any type of construction activity has taken place at a primary permittee's site, certified personnel provided by the primary permitte shall inspect: (a) all areas at the primary permittee's site where petroleum products are stored, used, or handled for spills and leaks from vehicles and equipment and (b) all locations at the primary permittee's site where vehicles enter or exit the site for evidence of off-site sediment tracking. These inspections must be conducted until a notice of termination is submitted.
2. Measure and record rainfall within disturbed areas of the site that have not met final stabilization once every 24 hours except any non-working saturday, non-working sunday and non-working federal holiday. The data collected for the purpose of compliance with this permit shall be representative of the monitored activity. Measurement of rainfall may be suspended if all areas of the site have undergone final stabilization or established a crop of annual vegetation and a seeding of target perennials appropriate for the region.
3. Certified personnel (provided by the primary permittee) shall inspect the following at least once every seven (7) calendar days and within 24 hours of the end of a storm that is 0.5 inches rainfall or greater (unless such storm ends after 5:00 pm on any friday or on any non-working saturday, non-working sunday or any non-working federal holiday in which case the inspection shall be completed by the end of the next business day and/or working day, whichever occurs first): (a) disturbed areas of the primary permittee's construction site; (b) areas used by the primary permittee for storage of materials that are exposed to precipitation; and (c) structural control measures. Erosion and sediment control measures identified in the plan applicable to the primary permittee's site shall be observed to ensure that they are operating correctly. Where discharge locations or points are accessible, they shall be inspected to ascertain whether erosion control measures are effective in preventing significant impacts to receiving water(s). For areas of a site that have undergone final stabilization or established a crop of annual vegetation and a seeding of target perennials appropriate for the region, the permittee must comply with part iv.d.4.a.(4). These inspections must be conducted until a notice of termination is submitted.
4. Certified personnel (provided by the primary permittee) shall inspected at least once per month during the term of this permit (i.e., until a notice of termination has been submitted) the areas of the site that have undergone final stabilization or established a crop of annual vegetation and a seeding target perennials appropriate for the region. These areas shall be inspected for evidence of, or the potential for, pollutants entering the drainage system and the receiving water(s). Erosion and sediment control measures identified in the plan shall be observed to ensure that they are operating correctly. Where discharge locations or points are accessible, they shall be inspected to ascertain whether erosion control measures are effective in preventing significant impacts to receiving water(s).
5. Based on the results of each inspection, the site description and the pollution prevention and control measures identified in the erosion, sedimentation and pollution control plan, the plan shall be revised as appropriate not later than seven (7) calendar days following each inspection. Implementation of such changes shall be made as soon as practical but in no case later than seven (7) calendar days following each inspection.
6. A report of each inspection that includes the name(s) of certified personnel making each inspection, the date(s) of each inspection, construction phase (i.e., initial, intermediate or final), major observations relating to the implementation of the erosion, sedimentation and pollution control plan and actions taken in accordance with part iv.d.4.a.(5) of the permit shall be made and retained at the site or be readily available at a designated alternate location until the entire site or that portion of a construction project that has been phased has undergone final stabilization and a notice of termination is submitted to epd. Such reports shall be readily available by end of the second business day and/or working day and shall identify all incidents of best management practices that have been properly installed and/or maintained as described in the plan. Where the report does not identify any incidents, the inspection report shall contain a certification that the best management practices are in compliance with the erosion, sedimentation and pollution control plan. The report shall be signed in accordance with part v.g.2. Of this permit

Site Grading Notes

1. Dimensions on buildings are for grading purposes only and are not to be used to lay-out footings. Refer to Structural Drawings for foundation information.
2. Grading contractor shall notify and cooperate with all utility companies or firms having facilities on or adjacent to the site before disturbing, altering, removing, relocating, adjusting or connecting to said facilities. Contractor shall pay all costs in connection with the alteration of or relocation of the facilities. Contractors shall raise or lower tops of existing manholes to remain as required to match finished grades.
3. Grading contractor shall cooperate and work with all other contractors performing work on this project to insure proper and timely completion of this project.
4. The grading contractor shall use whatever measures are required to prevent silt and construction debris from flowing onto adjacent properties. Contractor shall comply with all local erosion, conservation, and siltation ordinances. Contractors shall remove all temporary erosion control structures upon completion of permanent drainage facilities and not before the establishment of a stand of grass sufficient to prevent erosion.
5. For any work on the state or city right-of-way, the grading contractor shall:
   A. Not store material, excess dirt, or equipment in the right-of-way. The pavement shall be kept free from any mud or excavation waste from trucks or other equipment. On completion of the work, all excess material shall be removed from the right-of-way.
   B. Provide all necessary and adequate safety precautions such as signs, flags, light barricades, and flag-men as required by the local authorities and in accordance with solely responsible for and hold harmless the City, State, Architect, Engineer, and Owner from any claims for damage done to existing private property, public utilities, or to the traveling public.
   C. Complete work to the satisfaction of the City Public Works Department and obtain a letter from the Department stating that the work is acceptable.
7. Grading contractor shall take all available precautions to control dust. Contractor shall control dust by sprinkling, or by other methods as directed by Engineer and/or Owner's representative, at no additional cost to Owner.
8. Site grading contractor shall terminate all storm drain pipes five feet maximum from building unless otherwise noted.
9. Storm sewer lead-ins to building shall not be installed until building plans are completed and locations established on the architectural plans. Lead-ins may change 15' horizontally and 3' vertically prior to installation at no additional cost to the owner. Contractor shall request and receive written approval from prime contractor prior to installation of lead-ins. Contractor shall coordinate locations, size, and invert elevations of storm sewers with approved building plumbing plans.
10. All excavating is unclassified and shall include all materials encountered.
11. Before any machine work is done, contractor shall stake out and mark the items established by the site plan, control points shall be preserved at all times during the course of the project. Lack of proper working points and grade stakes may require satisfaction owner must approved staked items prior to construction.
12. Temporary erosion control devices to be installed prior to beginning of grading. Contractor shall maintain all temporary erosion control devices and shall remove silt contractor at least once a week.
13. Contractor to coordinate all work with other utility installations not covered in these plans, (Electric, Telephone, Gas, Cable, Etc.) and allow for their operations and construction to be performed.
14. Cut and fill slopes are not to exceed 3:1 unless otherwise noted.
15. In no case shall any paved areas be less than a slope of 1.0%. All accessible sidewalks and aisle slopes not to exceed 2% cross-slope.
16. Contractor shall repair or replace in-kind any damage that occurs as result of his work.
17. All linear footage for all utility pipes are approximate, actual installed quantities may vary.
18. Grading contractor shall restore to grade and compaction all areas disturbed by building construction prior to base and paving operations commencing.
19. Grading contractor shall maintain all weather construction access roads as required by general contractor.

Site Utility Notes

1. The site utility plan is for sanitary sewer and water line construction only. Do not use for grading or storm sewer construction.
2. All pipe lengths are horizontal distances and are approximate.
3. All domestic water and sanitary sewer stubs to be terminated 5 feet outside of the building unless otherwise noted. The end of these service lines shall be tightly plugged or capped and marked until such time as connection is made inside building by plumbing contractor.
4. Site utility contractor shall provide all the materials and appurtenances necessary for the complete installation of the utilities. All pipe and fittings shall be inspected by the Water Department Inspector prior to being covered. The inspector must also be present during pressure testing and disinfection of laterals and his signature of approval is required.
5. All work shall comply with all applicable codes, regulations, and/or local standards imposed by local utility and CITY OF JESUP.
6. The site utility contractor shall make arrangements with the local utility authorities for connection to the existing mains and pay all applicable fees.
7. All water lines shall have a minimum cover of 36" above top of pipe.
8. Contractor shall adjust location of proposed water lines as required to avoid conflicts with storm sewer or other utilities at no extra cost.
9. Based on the current edition of the international plumbing code, cleanouts are required at a maximum spacing of 100 feet on utility lead-ins to building. Contractor to provide a cleanout within 5 feet of building and at all bends.
10. The site utility contractor shall cooperate and work with all other contractors on the site.
11. All materials shall be U.L. listed and approved by the local utility company unless directed otherwise by the Engineer.
12. The existing utility facilities and locations shown on the drawings are taken from readily available information. The actual locations of the utility facilities may vary somewhat from the locations shown or indicated on the drawings. The site utility contractor shall contact all agencies with utility facilities in the vicinity of the work and shall locate all underground facilities before beginning work. The contractor shall project all utility facilities and repair any damages resulting from their work, in conformance with the contract documents and specifications and relocate if required.
13. All sanitary sewer pipe shall be SDR-26 meeting ASTM D3034 with gasket type joints meeting ASTM F477.
14. Utility lead-ins to building shall not be installed until building plans are completed and locations established on the architectural plumbing plans. Lead-ins my change 15' horizontally and 3' vertically prior to installations at no additional cost to the owner. Utility contractor shall request and receive written approval from prime contractor prior to installation of lead-ins. Location, size and invert elevations of sanitary sewer shall be coordinated with the approved plumbing plans for the building.
15. Building plumbing contractor shall pay all cost for water meters, meter boxes, valves, etc. to provide a complete job per local authority requirements.
16. Thrust blocks shall be provided at all tees, elbows, and bends of sufficient size to comply with minimum standards of N.F.P.A. – Existing soil conditions.
17. Should latent soil conditions necessitate, contractor shall install special supports for piping and/or appurtenances including the removal of unsuitable material and backfilling with gravel or other material. Contractor shall perform any such work as directed by the civil engineer and/or soils engineer at no cost to owner.
18. Contractor to coordinate all work with other utility installations not covered in these plans (Electric, Telephone, Gas, Cable, etc.) and allow for their operations and construction to be prepared.
19. The site utility contractor shall coordinate and pay for all sanitary sewer connections. Sanitary sewer connection final tie-in to the existing manhole(s) shall not be made until completion of the proposed system and all manholes have been brought above ground to insure sediment does not enter system. Lines shall be properly cleaned, if needed.
20. Site utility contractor to coordinate with irrigation contractor to provide power in conduit to irrigation controller per manufacturers recommendations. Verify exact location of controller with owner prior to installation.

UTILITY PROTECTION SERVICE 1-800-282-7411 GEORGIA811.COM DIAL 811

THIS DRAWING MAY NOT BE REPRODUCED WITHOUT WRITTEN PERMISSION FROM MAVERICK ENGINEERING, LLC

THE CONTRACTOR SHOULD VERIFY ALL LOCATIONS, GRADES, AND DIMENSIONS ILLUSTRATED ON THE PLANS AND WILL REPORT ANY DISCREPANCIES TO MAVERICK ENGINEERING, LLC.

MAVERICK ENGINEERING, LLC.
205 GENE ROLAND ROAD | JESUP, GA 31545
phone (912) 256-3704 www.maverickengineeringllc.com

SITE PLAN
HALL RICHARDS SENIOR CENTER


PARCEL NUMBER: JT-31, JT-32 & JT-33 JESUP, WAYNE COUNTY, GEORGIA

SHEET NAME:
GENERAL NOTES

REVISIONS:
1.
2.
3.
4.
5.
6.
7.
8.
9.
10.

INITIAL DATE: 4/17/2025
DRAWN BY: BDP
CHECKED BY: BDP
PROJECT #: 2025-01

SHEET NUMBER:
C 1.2



GEORGIA811.COM DIAL 811

THIS DRAWING MAY NOT BE REPRODUCED WITHOUT WRITTEN PERMISSION FROM MAVERICK ENGINEERING, LLC

THE CONTRACTOR SHOULD VERIFY ALL LOCATIONS, GRADES, AND DIMENSIONS ILLUSTRATED ON THE PLANS AND WILL REPORT ANY DISCREPANCIES TO MAVERICK ENGINEERING, LLC.

MAVERICK ENGINEERING, LLC.
205 GENE BLAND ROAD | JESUP, GA 31545
phone (912) 256-3704 www.maverickengineeringllc.com

SITE PLAN
HALL RICHARDS SENIOR CENTER


PARCEL NUMBER: J7-31, J7-32 & J7-33 JESUP, WAYNE COUNTY, GEORGIA


SHEET NAME:
EXISTING CONDITIONS

REVISIONS:
1.
2.
3.
4.
5.
6.
7.
8.
9.
10.

INITIAL DATE: 4/17/2025
DRAWN BY: BDP
CHECKED BY: BDP
PROJECT #: 2025-01

SHEET NUMBER:
C 2.1


EXISTING BASKETBALL COURT
EXISTING BASKETBALL COURT
N/F: JESUP-WAYNE COUNTY
TAX ID: J7-27
N/F: ST JOHNS
HOLINESS CHURCH
TAX ID: J7-67
N/F: DANNY &
DOROTHY
STEPHENS
TAX ID: J7-68
N/F: JOHNNY MATHIS
TAX ID: 107-30
EX 24" RCP
INV.: 73.86
EX DITCH
0.23' FROM BASKETBALL
COURT CORNER TO
PROPERTY LINE
RBF
N:587688.4052
E:745232.2208
PP
N:588028.3008
E:745087.2902
IPS
220.00'
N46°05'33"W
BUILDING
FFE 82.5
Property : 1
44000 SQ FT
1.01 ACRES
BLD CRNR
N:587801.9900
E:745279.1256
BLD CRNR
N:587732.6404
E:745551.1715
BLD CRNR
N:587688.4052
E:745232.2208
BLD CRNR
N:587757.3216
E:745236.1287
BLD CRNR
N:587687.9719
E:745308.1747
PL CRN
N:587850.4255
E:745223.0391
25' SETBACK
8' SETBACK
8' SETBACK
25' SETBACK
549°54'27"W
200.00'
N43°54'27"E
200.00'
N43°54'27"E
82.98'
N43°54'27"E
47.86'
N43°54'27"E
55.13'
S46°54'27"W
56.19'
S46°54'27"W
14.73'
62.0'
25.0'
12.0'
R5.00'
R5.00'
R10.00'
R10.00'
R10.00'
R10.00'
R25.00'
R25.00'
R12.37'
R5.77'
R15.00'
R15.00'
R15.00'
R15.00'
DROP SIDEWALK
DROP SIDEWALK
KILL DROP SIDEWALK
IN 5' FLUSH W/
SIDEWALK
KILL CURB IN 5'
FLUSH W/ SIDEWALK
KILL CURB IN 5'
FLUSH W/ SIDEWALK
KILL CURB IN 5'
FLUSH W/ SIDEWALK
KILL CURB IN 5'
KILL CURB IN 5'
KILL CURB IN 5'
KILL CURB IN 5'
FLUSH SIDEWALK
CONCRETE
WHEEL STOP
(TYP OF 6)
ONE WAY
ONE WAY
DO NOT
ENTER
DO NOT
ENTER
20.0'
20.0'
24.0'
20.0'
100.0'
26.0'
50.0'
30.0'
S46°05'33"E
162.01'
S46°05'33"E
187.01'
9.0'
25.00'
9.00'
25.00'
9.00'
CL INT
N:587772.0568
E:745192.0164
CL INT
N:587737.5780
E:745158.8280
CL INT
N:587607.8852
E:745293.5632
CL BEGIN
N:587697.8613
E:745120.5976
CL BEGIN
N:587562.6003
E:745254.5934
L=39.27' R=25.00'
CH=S71°05'33"E
CH DIS=35.36'
EX WATER
METER
220.00'
N46°05'33"W
1"W
1"W
4"SS
4"SS
4"SS



GRAPHIC SCALE

20 0 10 20 40 80

(IN FEET)
1 inch = 20 ft.

GEORGIA811.COM DIAL 811

THIS DRAWING MAY NOT BE REPRODUCED WITHOUT WRITTEN PERMISSION FROM MAVERICK ENGINEERING, LLC

THE CONTRACTOR SHOULD VERIFY ALL LOCATIONS, GRADES, AND DIMENSIONS ILLUSTRATED ON THE PLANS AND WILL REPORT ANY DISCREPANCIES TO MAVERICK ENGINEERING, LLC.

MAVERICK ENGINEERING, LLC.
205 GENE BLAND ROAD | JESUP, GA 31545
phone (912) 256-3704 www.mavrickengineeringllc.com

SITE PLAN
HALL RICHARDS
SENIOR CENTER


PARCEL NUMBER: J7-31, J7-32 & J7-33 JESUP, WAYNE COUNTY, GEORGIA

SHEET NAME:
PAVING, GRADING & DRIANAGE PLAN

REVISIONS:
1.
2.
3.
4.
5.
6.
7.
8.
9.
10.

INITIAL DATE: 4/17/2025
DRAWN BY: BDP
CHECKED BY: BDP
PROJECT #: 2025-01

SHEET NUMBER:
C 4.1



GEORGIA811.COM DIAL 811

THIS DRAWING MAY NOT BE REPRODUCED WITHOUT WRITTEN PERMISSION FROM MAVERICK ENGINEERING, LLC

THE CONTRACTOR SHOULD VERIFY ALL LOCATIONS, GRADES, AND DIMENSIONS ILLUSTRATED ON THE PLANS AND WILL REPORT ANY DISCREPANCIES TO MAVERICK ENGINEERING, LLC.

MAVERICK ENGINEERING, LLC.
205 GENE BLAND ROAD | JESUP, GA 31545
phone (912) 256-3704 www.maverickengineeringllc.com

SITE PLAN
HALL RICHARDS SENIOR CENTER

PARCEL NUMBER: JT-31, JT-32 & JT-33 JESUP, WAYNE COUNTY, GEORGIA

SHEET NAME:
UTILITY PLAN

REVISIONS:
1.
2.
3.
4.
5.
6.
7.
8.
9.
10.

INITIAL DATE: 4/17/2025
DRAWN BY: BDP
CHECKED BY: BDP
PROJECT #: 2025-01

SHEET NUMBER:
C 5.1

DS1
DISTURBED AREA STABILIZATION (WITH MULCHING ONLY)

DEFINITION
APPLYING PLANT RESIDUES OR OTHER SUITABLE MATERIALS, PRODUCED ON THE SITE IF POSSIBLE, TO THE SOIL SURFACE.

PURPOSE
1. TO REDUCE RUNOFF EROSION
2. TO CONSERVE MOISTURE
3. TO PREVENT SURFACE COMPACTION OR CRUSTING
4. TO CONTROL UNDESIRABLE VEGETATION
5. TO INCREASE BIOLOGICAL ACTIVITY IN THE SOIL.

REQUIREMENT FOR REGULATORY COMPLIANCE
MULCH OR TEMPORARY GRASSING SHALL BE APPLIED TO ALL EXPOSED AREAS WITHIN 14 DAYS OF DISTURBANCE. MULCH CAN BE USED AS A SINGULAR EROSION CONTROL DEVICE FOR UP TO SIX MONTHS, BUT IT SHALL BE APPLIED AT THE APPROPRIATE DEPTH, DEPENDING ON THE MATERIAL USED, ANCHORED, AND HAVE A CONTINUOUS 90% COVER OR GREATER OF THE SOIL SURFACE. MAINTENANCE SHALL BE REQUIRED TO MAINTAIN APPROPRIATE DEPTH AND 90% COVER. TEMPORARY VEGETATION MAY BE EMPLOYED INSTEAD OF MULCH IF THE AREA WILL REMAIN UNDISTURBED FOR LESS THAN SIX MONTHS. IF AN AREA WILL REMAIN UNDISTURBED FOR GREATER THAN SIX MONTHS, PERMANENT VEGETATIVE TECHNIQUES SHALL BE EMPLOYED.

SPECIFICATIONS
MULCHING WITHOUT SEEDING
THIS STANDARD APPLIES TO GRADES OR CLEARED AREAS WHERE SEEDINGS MAY NOT HAVE A SUITABLE GROWING SEASON TO PRODUCE AN EROSION RETARDANT COVER, BUT CAN BE STABILIZED WITH A MULCH COVER.

SITE PREPARATION
1. GRADE TO PERMIT THE USE OF EQUIPMENT FOR APPLYING AND ANCHORING MULCH.
2. INSTALL NEEDED EROSION CONTROL MEASURES AS REQUIRED SUCH AS DIKES, DIVERSIONS, BERMS, TERRACES AND SEDIMENT BARRIERS.
3. LOOSEN COMPACT SOIL TO A MINIMUM DEPTH OF 3 INCHES.

MULCHING MATERIALS
SELECT ONE OF THE FOLLOWING MATERIALS AND APPLY AT THE DEPTH INDICATED:
1. DRY STRAW OR HAY SHALL BE APPLIED AT A DEPTH OF 2 TO 4 INCHES PROVIDING COMPLETE SOIL COVERAGE. ONE ADVANTAGE OF THIS MATERIAL IS EASY APPLICATION.
2. WOOD WASTE (CHIPS, SAWDUST OR BARK) SHALL BE APPLIED AT A DEPTH OF 2 TO 3 INCHES. ORGANIC MATERIAL FROM THE CLEARING STAGE OF DEVELOPMENT SHOULD REMAIN ON SITE, BE CHIPPED, AND APPLIED AS MULCH. THIS METHOD OF MULCHING CAN GREATLY REDUCE EROSION CONTROL COSTS.
3. POLYETHYLENE FILM SHALL BE SECURED OVER BANKS OR STOCKPILED SOIL MATERIAL FOR TEMPORARY PROTECTION. THIS MATERIAL CAN BE SALVAGED AND REUSED.

APPLYING MULCH
WHEN MULCH IS USED WITHOUT SEEDING, MULCH SHALL BE APPLIED TO PROVIDE FULL COVERAGE OF THE EXPOSED AREA.
1. DRY STRAW OR HAY MULCH AND WOOD CHIPS SHALL BE APPLIED UNIFORMLY BY HAND OR BY MECHANICAL EQUIPMENT.
2. IF THE AREA WILL EVENTUALLY BE COVERED WITH PERENNIAL VEGETATION, 20-30 POUNDS OF NITROGEN PER ACRE IN ADDITION TO THE NORMAL AMOUNT SHALL BE APPLIED TO OFFSET THE UPTAKE OF NITROGEN CAUSED BY THE DECOMPOSITION OF THE ORGANIC MULCHES.
3. APPLY POLYETHYLENE FILM ON EXPOSED AREAS.

ANCHORING MULCH
1. STRAW OR HAY MULCH CAN BE PRESSED INTO THE SOIL WITH A DISK HARROW WITH THE DISK SET STRAIGHT OR WITH A SPECIAL "PACKER DISK." DISKS MAY BE SMOOTH OR SERRATED AND SHOULD BE 20 INCHES OR MORE IN DIAMETER AND 8 TO 12 INCHES APART. THE EDGES OF THE DISK SHOULD BE DULL ENOUGH NOT TO CUT THE MULCH BUT TO PRESS IT INTO THE SOIL LEAVING MUCH OF IT IN AN ERECT POSITION. STRAW OR HAY MULCH SHALL BE ANCHORED IMMEDIATELY AFTER APPLICATION. STRAW OR HAY MULCH SPREAD WITH SPECIAL BLOWER-TYPE EQUIPMENT MAY BE ANCHORED. TACKIFIERS, BINDERS AND HYDRAULIC MULCH WITH TACKIFIERS SPECIFICALLY DESIGNED FOR TACKING STRAW CAN BE SUBSTITUTED FOR EMULSIFIED ASPHALT. PLEASE REFER TO SPECIFICATION TACKIFIERS. PLASTIC MESH OR NETTING WITH MESH NO LARGER THAN ONE INCH BY ONE INCH SHALL BE INSTALLED ACCORDING TO MANUFACTURER'S SPECIFICATIONS.
2. NETTING OF THE APPROPRIATE SIZE SHALL BE USED TO ANCHOR WOOD WASTE. OPENINGS OF THE NETTING SHALL NOT BE LARGER THAN THE AVERAGE SIZE OF THE WOOD WASTE CHIPS.
3. POLYETHYLENE FILM SHALL BE ANCHOR TRENCHED AT THE TOP AS WELL AS INCREMENTALLY AS NECESSARY.

APPLICATION RATE FOR EACH TYPE OF SOIL ENCOUNTERED ON THE SITE.

MULCHING: MULCHING IS REQUIRED FOR ALL PERMANENT VEGETATION APPLICATIONS. MULCHING APPLIED TO SEEDED AREAS SHALL ACHIEVE 75% SOIL COVER. SELECT THE MULCHING MATERIAL FROM THE FOLLOWING AND APPLY AS INDICATED.
1. DRY STRAW OR DRY HAY OF GOOD QUALITY AND FREE OF WEED SEEDS CAN BE USED. DRY STRAW SHALL BE APPLIED AT THE RATE OF 2 TONS PER ACRE. DRY HAY SHALL BE APPLIED AT A RATE OF 2 1/2 TONS PER ACRE.
2. WOOD CELLULOSE MULCH OR WOOD PULP FIBER SHALL BE USED WITH HYDRAULIC SEEDING. IT SHALL BE APPLIED AT A RATE OF 500 LBS PER ACRE. DRY STRAW R DRY HAY SHALL BE APPLIED AFTER HYDRAULIC SEEDING.
3. ONE THOUSAND POUNDS OF WOOD CELLULOSE OF WOOD PULP FIBER, WHICH INCLUDES A TACKIFIER SHALL BE USED WITH HYDRAULIC SEEDING ON SLOPES GREATER THAN 3/4:1 OR STEEPER.
4. SERICEA LESPEDEZA HAY CONTAINING MATURE SEED SHALL BE APPLIED AT A RATE OF THREE TONS PER ACRE.
5. PINE STRAW OR PINE BARK SHALL BE APPLIED AT A THICKNESS OF 3" FOR BEDDING PURPOSES. OTHER SUITABLE MATERIALS IN SUFFICIENT QUANTITIES MAY BE USED WHERE ORNAMENTALS OR OTHER GROUND COVERS ARE PLANTED. THIS IS NOT APPROPRIATE FOR SEEDED AREAS.
6. WHEN USING TEMPORARY EROSION CONTROL BLANKETS OR BLOCK SOD, MULCHING IS NOT REQUIRED.

MULCHING
NOT TO SCALE
Ds1

DS2

DISTURBED AREA STABILIZATION (WITH TEMPORARY SEEDING)

DEFINITION
THE ESTABLISHMENT OF TEMPORARY VEGETATIVE COVER WITH FAST GROWING SEEDINGS FOR SEASONAL PROTECTION ON DISTURBED OR DENUDED AREAS.

PUPROSE
TO REDUCE RUNOFF AND SEDIMENT DAMAGE OF DOWN STREAM RESOURCES
TO PROTECT THE SOIL SURFACE FROM EROSION
TO IMPROVE WILDLIFE HABITAT
TO IMPROVE AESTHETICS
TO IMPROVE TILTH, INFILTRATION AND AERATION AS WELL AS ORGANIC MATTER FOR PERMANENT PLANTINGS

REQUIREMENT FOR REGULATORY COMPLIANCE
MULCH OR TEMPORARY GRASSING SHALL BE APPLIED TO ALL EXPOSED AREAS WITHIN 14 DAYS OF DISTUR- BANCE. TEMPORARY GRASSING, INSTEAD OF MULCH, CAN BE APPLIED TO ROUGH GRADED AREAS THAT WILL BE EXPOSED FOR LESS THAN SIX MONTHS. IF AN AREA IS EXPECTED TO BE UNDISTURBED FOR LONGER THAN SIX MONTHS, PERMANENT PERENNIAL VEGETATION SHALL BE USED. IF OPTIMUM PLANTING CONDITIONS FOR TEMPORARY GRASSING IS LACKING, MULCH CAN BE USED AS
A SINGULAR EROSION CONTROL DEVICE FOR UP TO SIX MONTHS BUT IT SHALL BE APPLIED AT THE APPROPRIATE DEPTH, ANCHORED, AND HAVE A CONTINUOUS 90% COVER OR GREATER OF THE SOIL SURFACE.

CONDITIONS
TEMPORARY GRASSING, INSTEAD OF MULCH, CAN BE APPLIED TO ROUGH GRADED AREAS THAT WILL BE EXPOSED FOR LESS THAN SIX MONTHS. TEMPORARY VEGETATIVE MEASURES SHOULD BE COORDINATED WITH PERMANENT MEASURES TO ASSURE ECONOMICAL AND EFFECTIVE STABILIZATION. MOST TYPES OF TEMPORARY VEGETATION ARE IDEAL TO USE AS COMPANION CROPS UNTIL THE PERMANENT VEGETATION IS ESTABLISHED.

SPECIFICATIONS
GRADING AND SHAPING
EXCESSIVE WATER RUN-OFF SHALL BE REDUCED BY PROPERLY DESIGNED AND INSTALLED EROSION CONTROL PRACTICES SUCH AS CLOSED DRAINS, DITCHES, DIKES, DIVERSIONS, SEDIMENT BARRIERS AND OTHERS. NO SHAPING OR GRADING IS REQUIRED IF SLOPES CAN BE STABILIZED BY HAND-SEEDED VEGETATION OR IF HYDRAULIC SEEDING EQUIPMENT IS TO BE USED.

SEEDBED PREPARATION
WHEN A HYDRAULIC SEEDER IS USED, SEEDBED PREPARATION IS NOT REQUIRED. WHEN USING CONVENTIONAL OR HANDSEEDING, SEEDBED PREPARATION IS NOT REQUIRED IF THE SOIL MATERIAL IS LOOSE AND NOT SEALED BY RAINFALL. WHEN SOIL HAS BEEN SEALED BY RAINFALL OR CONSISTS OF SMOOTH CUT SLOPES, THE SOIL SHALL BE PITTED, TRENCHED OR OTHERWISE SCARIFIED TO PROVIDE A PLACE FOR SEED TO LODGE AND GERMINATE.

LIME AND FERTILIZER
AGRICULTURAL LIME IS REQUIRED UNLESS SOIL TESTS INDICATE OTHERWISE. APPLY AGRICULTURAL LIME AT A RATE OF ONE TON PER ACRE. GRADED AREAS REQUIRE LIME APPLICATION. SOILS CAN BE TESTED TO DETERMINE IF FERTILIZER IS NEEDED. ON REASONABLY FERTILE SOILS OR SOIL MATERIAL, FERTILIZER IS NOT REQUIRED. FOR SOILS WITH VERY LOW FERTILITY, 500 TO 700 POUNDS OF 10-10-10 FERTILIZER OR THE EQUIVALENT PER ACRE (12-16 LBS./1,000 SQ. FT.) SHALL BE APPLIED. FERTILIZER SHOULD BE APPLIED BEFORE LAND PREPARATION AND INCORPORATED WITH A DISK, RIPPER OR CHISEL.

SEEDING
SELECT A GRASS OR GRASS-LEGUME MIXTURE SUITABLE TO THE AREA AND SEASON OF THE YEAR. SEED SHALL BE APPLIED UNIFORMLY BY HAND, CYCLONE SEEDER, DRILL, CULTIPACKER SEEDER, OR HYDRAULIC SEEDER (SLURRY INCLUDING SEED AND FERTILIZER). DRILL OR CULTIPACKER SEEDERS SHOULD NORMALLY PLACE SEED ONE-QUARTER TO ONE-HALF INCH DEEP. APPROPRIATE DEPTH OF PLANTING IS TEN TIMES THE SEED DIAMETER. SOIL SHOULD BE "RAKED" LIGHTLY TO COVER SEED WITH SOIL IF SEEDED BY HAND.

MULCHING
TEMPORARY VEGETATION CAN, IN MOST CASES, BE ESTABLISHED WITHOUT THE USE OF MULCH. MULCH WITHOUT SEEDING SHOULD BE CONSIDERED FOR SHORT TERM PROTECTION. REFER TO DS1-DISTURBED AREA STABILIZATION (WITH MULCHING ONLY).

IRRIGATION
DURING TIMES OF DROUGHT, WATER SHALL BE APPLIED AT A RATE NOT CAUSING RUNOFF AND EROSION. THE SOIL SHALL BE THOROUGHLY WETTED TO A DEPTH THAT WILL INSURE GERMINATION OF THE SEED. SUBSEQUENT APPLICATIONS SHOULD BE MADE WHEN NEEDED.

SEEDING RATES FOR TEMPORARY SEEDING.

SPECIES	RATE PER 1,000 SQ.FT.	RATE PER ACRE *	PLANTING DATES**
RYE	3.9 LBS.	3 BU	9/1 - 3/1
RYE GRASS	0.9 LBS.	40 LBS.	8/15 - 4/1
ANNUAL LESPEDEZA	0.9 LBS.	40 LBS.	1/15 -9/15
WEEPING LOVEGRASS	0.1 LBS.	4 LBS.	2/15 - 6/15
SUNDANGRASS	1.4 LBS.	60 LBS.	3/1 - 8/1
BROWN MILLET	0.9 LBS.	40 LBS.	4/1 - 7/15
WHEAT	4.1 LBS.	3 BU	9/15 - 2/1

* UNUSUAL SITE CONDTIONS MAY REQUIRE HEAVIER SEEDING RATES.
** SEEDING DATES MAY NEED TO BE ALTERED TO FIT TMPERATURE VARIATIONS AND CONDITIONS.

GRASSING TEMPORARY
NOT TO SCALE
Ds2

DU

DUST CONTROL ON DISTURBED AREAS

DEFINITION
CONTROLLING SURFACE AND AIR MOVEMENT OF DUST ON CONSTRUCTION SITES, ROADS, AND DEMOLITION SITES.

CONDITIONS
THIS PRACTICE IS APPLICABLE TO AREAS SUBJECT TO SURFACE AND AIR MOVEMENT OF DUST WHERE ON AND OFF-SITE DAMAGE MAY OCCUR WITHOUT TREATMENT.

METHOD AND MATERIALS
A. TEMPORARY METHODS

MULCHES. SEE STANDARD DS1-DISTURBED AREA STABILIZATION (WITH MULCHING ONLY). SYNTHETIC RESINS MAY BE USED INSTEAD OF ASPHALT TO BIND MULCH MATERIAL. REFER TO STANDARD TB-TACKIFIERS AND BINDERS. RESINS SUCH AS CURASOL OR TERRATACK SHOULD BE USED ACCORDING TO MANUFACTURER'S RECOMMENDATIONS.

VEGETATIVE COVER. SEE STANDARD DS2- DISTURBED AREA STABILIZATION (WITH TEMPORARY SEEDING)

SPRAY-ON ADHESIVES. THESE ARE USED ON MINERAL SOILS (NOT EFFECTIVE ON MUCK SOILS) KEEP TRAFFIC OFF THESE AREAS. REFER TO STANDARD TB-TACKIFIERS AND BINDERS.

TILLAGE. THIS PRACTICE IS DESIGNED TO ROUGHEN AND BRING CLODS TO THE SURFACE. IT IS AN EMERGENCY MEASURE WHICH SHOULD BE USED BEFORE WIND EROSION STARTS. BEGIN PLOWING ON WINDWARD SIDE OF SITE. CHISEL-TYPE PLOWS SPACED ABOUT 12 INCHES APART, SPRING-TOOTHED HARROWS, AND SIMILAR PLOWS ARE EXAMPLES OF EQUIPMENT WHICH MAY PRODUCE THE DESIRED EFFECT.

IRRIGATION. THIS IS GENERALLY DONE AS AN EMERGENCY TREATMENT. SITE IS SPRINKLED WITH WATER UNTIL THE SURFACE IS WET. REPEAT AS NEEDED.

BARRIERS. SOLID BOARD FENCES, SNOW FENCES, BURLAP FENCES, CRATE WALLS, BALES OF HAY AND SIMILAR MATERIAL CAN BE USED TO CONTROL AIR CURRENTS AND SOIL BLOWING. BARRIERS PLACED AT RIGHT ANGLES TO PREVAILING CURRENTS AT INTERVALS OF ABOUT 15 TIMES THEIR HEIGHT ARE EFFECTIVE IN CONTROLLING WIND EROSION.

CALCIUM CHLORIDE. APPLY AT RATE THAT WILL KEEP SURFACE MOIST. MAY NEED RETREATMENT.

B. PERMANENT METHODS

PERMANENT VEGETATION. SEE STANDARD DS3-DISTURBED AREA STABILIZATION (WITH PERMANENT VEGETATION), EXISTING TREES AND LARGE SHRUBS MAY AFFORD VALUABLE PROTECTION IF LEFT IN PLACE.

TOPSOILING. THIS ENTAILS COVERING THE SURFACE WITH LESS EROSIVE SOIL MATERIAL. SEE STANDARD TP-TOPSOILING.

STONE. COVER SURFACE WITH CRUSHED STONE OR COARSE GRAVEL. SEE STANDARD CR-CONSTRUCTION ROAD STABILIZATION.

DUST CONTROL
NOT TO SCALE
Du

DS3

DISTURBED AREA STABILIZATION (WITH PERMANENT VEGETATION)

DEFINITION
THE PLANTING OF PERENNIAL VEGETATION SUCH AS TREES, SHRUBS, VINES, GRASSES, OR LEGUMES ON EXPOSED AREAS FOR FINAL PERMANENT STABILIZATION. PERMANENT PERENNIAL VEGETATION SHALL BE USED TO ACHIEVE FINAL STABILIZATION.

CONDITIONS
PERMANENT PERENNIAL VEGETATION IS USED TO PROVIDE A PROTECTIVE COVER FOR EXPOSED AREAS INCLUDING CUTS, FILLS, DAMS, AND OTHER DENUDED AREAS.

SPECIFICATIONS
GRADING AND SHAPING
GRADING AND SHAPING MAY NOT BE REQUIRED WHERE HYDRAULIC SEEDING AND FERTILIZING EQUIPMENT IS TO BE USED. VERTICAL BANKS SHALL BE SLOPED TO ENABLE PLANT ESTABLISHMENT.
WHEN CONVENTIONAL SEEDING AND FERTILIZING ARE TO BE DONE, GRADE AND SHAPE WHERE FEASIBLE AND PRACTICAL, SO THAT EQUIPMENT CAN BE USED SAFELY AND EFFICIENTLY DURING SEEDBED PREPARATION, SEEDING, MULCHING AND MAINTENANCE OF THE VEGETATION.
CONCENTRATIONS OF WATER THAT WILL CAUSE EXCESSIVE SOIL EROSION SHALL BE DIVERTED TO A SAFE OUTLET. DIVERSIONS AND OTHER TREATMENT PRACTICES SHALL CONFORM WITH THE APPROPRIATE STANDARDS AND SPECIFICATIONS.

SEEDBED PREPARATION
SEEDBED PREPARATION MAY NOT BE REQUIRED WHERE HYDRAULIC SEEDING AND FERTILIZING EQUIPMENT IS TO BE USED. WHEN CONVENTIONAL SEEDING IS TO BE USED, SEEDBED PREPARATION WILL BE DONE AS FOLLOWS:

BROADCAST PLANTINGS
1. TILLAGE AT A MINIMUM, SHALL ADEQUATELY LOOSEN THE SOIL TO A DEPTH OF 4 TO 6 INCHES; ALLEVIATE COMPACTION; INCORPORATE LIME AND FERTILIZER; SMOOTH AND FIRM THE SOIL; ALLOW FOR THE PROPER PLACEMENT OF SEED, SPRIGS, OR PLANTS; AND ALLOW FOR THE ANCHORING OF STRAW OR HAY MULCH IF A DISK IS TO BE USED.
2. TILLAGE MAY BE DONE WITH ANY SUITABLE EQUIPMENT.
3. TILLAGE SHOULD BE DONE ON THE CONTOUR WHERE FEASIBLE.
4. ON SLOPES TOO STEEP FOR THE SAFE OPERATION OF TILLAGE EQUIPMENT, THE SOIL SURFACE SHALL BE PITTED OR TRENCHED ACROSS THE SLOPE WITH APPROPRIATE HAND TOOLS TO PROVIDE TWO PLACES 6 TO 8 INCHES APART IN WHICH SEED MAY LODGE AND GERMINATE. HYDRAULIC SEEDING MAY ALSO BE USED.

INDIVIDUAL PLANTS
1. WHERE INDIVIDUAL PLANTS ARE TO BE SET, THE SOIL SHALL BE PREPARED BY EXCAVATING HOLES, OPENING FURROWS, OR DIBBLE PLANTING.
2. FOR NURSERY STOCK PLANTS, HOLES SHALL BE LARGE ENOUGH TO ACCOMMODATE ROOTS WITHOUT CROWDING.
3. WHERE PINE SEEDLINGS ARE TO BE PLANTED, SUBSOIL UNDER THE ROW 36 INCHES DEEP ON THE CONTOUR FOUR TO SIX MONTHS PRIOR TO PLANTING. SUBSOILING SHOULD BE DONE WHEN THE SOIL IS DRY, PREFERABLY IN AUGUST OR SEPTEMBER.

PLANTING
HYDRAULIC SEEDING
MIX THE SEED (INOCULATED IF NEEDED), FERTILIZER, AND WOOD CELLULOSE OR WOOD PULP FIBER MULCH WITH WATER AND APPLY IN A SLURRY UNIFORMLY OVER THE AREA TO BE TREATED. APPLY WITHIN ONE HOUR AFTER THE MIXTURE IS MADE.

CONVENTIONAL SEEDING
SEEDING WILL BE DONE ON A FRESHLY PREPARED AND FIRMED SEEDBED. FOR BROADCAST PLANTING, USE A CULTIPACKER SEEDER, DRILL, ROTARY SEEDER, OTHER MECHANICAL SEEDER, OR HAND SEEDING TO DISTRIBUTE THE SEED UNIFORMLY OVER THE AREA TO BE TREATED. COVER THE SEED LIGHTLY WITH 1/8 TO ¼ INCH OF SOIL FOR SMALL SEED AND ½ TO 1 INCH FOR LARGE SEED WHEN USING A CULTIPACKER OR OTHER SUITABLE EQUIPMENT.

NO-TILL SEEDING
NO-TILL SEEDING IS PERMISSIBLE INTO ANNUAL COVER CROPS WHEN PLANTING IS DONE FOLLOWING MATURITY OF THE COVER CROP OR IF THE TEMPORARY COVER STAND IS SPARSE ENOUGH TO ALLOW ADEQUATE GROWTH OF THE PERMANENT (PERENNIAL) SPECIES. NO-TILL SEEDING SHALL BE DONE WITH APPROPRIATE NO-TILL SEEDING EQUIPMENT. THE SEED MUST BE UNIFORMLY DISTRIBUTED AND PLANTED AT THE PROPER DEPTH.

INDIVIDUAL PLANTS
SHRUBS, VINES AND SPRIGS MAY BE PLANTED WITH APPROPRIATE PLANTERS OR HAND TOOLS. PINE TREES SHALL BE PLANTED MANUALLY IN THE SUBSOIL FURROW. EACH PLANT SHALL BE SET IN A MANNER THAT WILL AVOID CROWDING THE ROOTS. NURSERY STOCK PLANTS SHALL BE PLANTED AT THE SAME DEPTH OR SLIGHTLY DEEPER THAN THEY GREW AT THE NURSERY. THE TIPS OF VINES AND SPRIGS MUST BE AT OR SLIGHTLY ABOVE THE GROUND SURFACE. WHERE INDIVIDUAL HOLES ARE DUG, FERTILIZER SHALL BE PLACED IN THE BOTTOM OF THE HOLE, TWO INCHES OF SOIL SHALL BE ADDED AND THE PLANT SHALL BE SET IN THE HOLE.

MULCHING
MULCH IS REQUIRED FOR ALL PERMANENT VEGETATION APPLICATIONS. MULCH APPLIED TO SEEDED AREAS SHALL ACHIEVE 75% SOIL COVER. SELECT THE MULCHING MATERIAL FROM THE FOLLOWING AND APPLY AS INDICATED:

1. DRY STRAW OR DRY HAY OF GOOD QUALITY AND FREE OF WEED SEEDS CAN BE USED. DRY STRAW SHALL BE APPLIED AT THE RATE OF 2 TONS PER ACRE. DRY HAY SHALL BE APPLIED AT A RATE OF 2 ½ TONS PER ACRE.
2. WOOD CELLULOSE MULCH OR WOOD PULP FIBER SHALL BE USED WITH HYDRAULIC SEEDING. IT SHALL BE APPLIED AT THE RATE OF 500 POUNDS PER ACRE. DRY STRAW OR DRY HAY SHALL BE APPLIED (AT THE RATE INDICATED ABOVE) AFTER HYDRAULIC SEEDING.
3. ONE THOUSAND POUNDS OF WOOD CELLULOSE OR WOOD PULP FIBER, WHICH INCLUDES A TACKIFIER, SHALL BE USED WITH HYDRAULIC SEEDING ON SLOPES 3/4:1 OR STEEPER.
4. SERICEA LESPEDEZA HAY CONTAINING MATURE SEED SHALL BE APPLIED AT A RATE OF THREE TONS PER ACRE.
5. PINE STRAW OR PINE BARK SHALL BE APPLIED AT A THICKNESS OF 3 INCHES FOR BEDDING PURPOSES. OTHER SUITABLE MATERIALS IN SUFFICIENT QUANTITY MAY BE USED WHERE ORNAMENTALS OR OTHER GROUND COVERS ARE PLANTED. THIS IS NOT APPROPRIATE FOR SEEDED AREAS.
6. WHEN USING TEMPORARY EROSION CONTROL BLANKETS OR BLOCK SOD, MULCHING IS NOT REQUIRED.
7. BITUMINOUS TREATED ROVING MAY BE APPLIED ON PLANTED AREAS ON SLOPES, IN DITCHES OR DRY WATERWAYS TO PREVENT EROSION. BITUMINOUS TREATED ROVING SHALL BE APPLIED WITHIN 24 HOURS AFTER AN AREA HAS BEEN PLANTED. APPLICATION RATES AND MATERIALS MUST MEET GEORGIA DEPARTMENT OF TRANSPORTATION SPECIFICATIONS.

WOOD CELLULOSE AND WOOD PULP FIBERS SHALL NOT CONTAIN GERMINATION OR GROWTH INHIBITING FACTORS. THEY SHALL BE EVENLY DISPERSED WHEN AGITATED IN WATER. THE FIBERS SHALL CONTAIN A DYE TO ALLOW VISUAL METERING AND AID IN UNIFORM APPLICATION DURING SEEDING.

APPLYING MULCH
STRAW OR HAY MULCH WILL BE SPREAD UNIFORMLY WITHIN 24 HOURS AFTER SEEDING AND/OR PLANTING THE MULCH MAY BE SPREAD BY BLOWER-TYPE SPREADING EQUIPMENT, OTHER SPREADING EQUIPMENT OR BY HAND. MULCH SHALL BE APPLIED TO COVER 75% OF THE SOIL SURFACE.
WOOD CELLULOSE OR WOOD FIBER MULCH SHALL BE APPLIED UNIFORMLY WITH HYDRAULIC SEEDING EQUIPMENT.

ANCHORING MULCH
ANCHOR STRAW OR HAY MULCH IMMEDIATELY AFTER APPLICATION BY ONE OF THE FOLLOWING METHODS:
1. EMULSIFIED ASPHALT CAN BE (A) SPRAYED UNIFORMLY ONTO THE MULCH AS IT IS EJECTED FROM THE BLOWER MACHINE OR (B) SPRAYED ON THE MULCH IMMEDIATELY FOLLOWING MULCH APPLICATION WHEN STRAW OR HAY IS SPREAD BY METHODS OTHER THAN SPECIAL BLOWER EQUIPMENT.

THE COMBINATION F ASPHALT EMULSION AND WATER SHALL CONSIST OF A HOMOGENEOUS MIXTURE SATISFACTORY FOR SPRAYING. THE MIXTURE SHALL CONSIST OF 100 GALLONS OF GRADE SS-1H OR CSS-1H EMULSIFIED ASPHALT AND 100 GALLONS OF WATER PER TON OF MULCH.
CARE SHALL BE TAKEN AT ALL TIMES TO PROTECT STATE WATERS, THE PUBLIC, ADJACENT PROPERTY, PAVEMENTS, CURBS, SIDEWALKS, AND ALL OTHER STRUCTURES FROM ASPHALT DISCOLORATION.

2. HAY AND STRAW MULCH SHALL BE PRESSED INTO THE SOIL IMMEDIATELY AFTER THE MULCH IS SPREAD. A SPECIAL "PACKER DISK" OR DISK HARROW WITH THE DISKS SET STRAIGHT MAY BE USED. THE DISKS MAY BE SMOOTH OR SERRATED AND SHOULD BE 20 INCHES OR MORE IN DIAMETER AND 8 TO 12 INCHES APART. THE EDGES OF THE DISKS SHALL BE DULL ENOUGH TO PRESS THE MULCH INTO THE GROUND WITHOUT CUTTING IT, LEAVING MUCH OF IT IN AN ERECT POSITION. MULCH SHALL NOT BE PLOWED INTO THE SOIL.
3. SYNTHETIC TACKIFIERS OR BINDERS APPROVED BY GDOT SHALL BE APPLIED IN CONJUNCTION WITH OR IMMEDIATELY AFTER THE MULCH IS SPREAD. SYNTHETIC TACKIFIERS SHALL BE MIXED AND APPLIED ACCORDING TO MANUFACTURER'S SPECIFICATIONS. REFER TO TB-TACKIFIERS AND BINDERS.
4. RYE OR WHEAT CAN BE INCLUDED WITH FALL AND WINTER PLANTINGS TO STABILIZE THE MULCH. THEY SHALL BE APPLIED AT A RATE OF ONE-QUARTER TO ONE HALF BUSHEL PER ACRE.
5. PLASTIC MESH OR NETTING WITH MESH NO LARGER THAN ONE INCH BY ONE INCH MAY BE NEEDED TO ANCHOR STRAW OR HAY MULCH ON UNSTABLE SOILS AND CONCENTRATED FLOW AREAS. THESE MATERIALS SHALL BE INSTALLED AND ANCHORED ACCORDING TO MANUFACTURER'S SPECIFICATIONS.

IRRIGATION
IRRIGATION SHALL BE APPLIED AT A RATE THAT WILL NOT CAUSE RUNOFF.


GRASSING PERMANENT
NOT TO SCALE
Ds3

TABLE 6-5.1 FERTILIZER REQUIREMENTS

TYPE OF SPECIES	YEAR	ANALYSIS FOR EQUIVALENT N-P-K	RATE	N TOP DRESSING RATE
1. COOL SEASON GRASSES	FIRST	6-12-12	1500 LBS./AC.	50-100 LBS./AC. 1/2/
	SECOND	6-12-12	1000 LBS./AC.	-
	MAINTENANCE	10-10-10	400 LBS./AC.	30
2. COOL SEASON GRASSES AND LEGUMES	FIRST	6-12-12	1500 LBS./AC.	0-50 LBS./AC. 1/
	SECOND	0-10-10	1000 LBS./AC.	-
	MAINTENANCE	0-10-10	400 LBS./AC.	-
3. GROUND COVERS	FIRST	10-10-10	1300 LBS./AC.	-
	SECOND	10-10-10	1300 LBS./AC.	-
	MAINTENANCE	10-10-10	1100 LBS./AC.	-
4. PINE SEEDLINGS	FIRST	20-10-6	ONE 21-GRAM PELLET PER SEEDING PLACED IN THE CLOSING HOLE	-
5. SHRUB LESPEDEZA	FIRST	0-10-10	700 LBS./AC.	-
	MAINTENANCE	0-10-10	700 LBS./AC.4/	-
6. TEMPORARY COVER CROPS SEEDED ALONE	FIRST	10/10/2010	500 LBS./AC.	30 LB./ACRE/ 5/
7. WARM SEASON GRASSES	FIRST	6-12-12	1500 LBS./AC.	50-100 LBS./AC. 2/6/
	SECOND	6-12-12	1000 LBS./AC.	50-100 LBS./AC. 2/
	MAINTENANCE	10-10-10	400 LBS./AC.	30 LBS./AC.
8. WARM SEASON GRASSES AND LEGUMES	FIRST	6-12-12	1500 LBS./AC.	50 LBS./AC./6/
	SECOND	0-10-10	1000 LBS./AC.	
	MAINTENANCE	0-10-10	400 LBS./AC.	

1/ APPLY IN SPRING FOLLOWING SEEDING.
2/ APPLY IN SPLIT APPLICATIONS WHEN HIGH RATES ARE USED.
3/ APPLY IN 3 SPLIT APPLICATIONS.
4/ APPLY WHEN PLANTS ARE PRUNED.
5/ APPLY TO GRASS SPECIES ONLY.
6/ APPLY WHEN PLANTS GROW TO A HEIGHT OF 2 TO 4 INCHES.

Month	Temporary Cover Ds2	Rate per Acre Seeded Alone	Rate per Acre Added To Mix	Permanent Cover Ds3	Rate per Acre Seeded Alone	Rate per Acre Added To Mix
January	Rye grass	40 lbs.	--	Unhulled Bermuda	10 lbs.	6 lbs.
	Rye	3 bu.	.5 bu.	Sericea Lespedeza (1)	75 lbs.	--
February	Annual Lespedeza	40 lbs.	10 lbs.	Unhulled Bermuda	10 lbs.	6 lbs.
	Rye grass	40 lbs.	--	Sericea Lespedeza (1)	75 lbs.	--
	Rye	3 bu.	.5 bu.			
March	Weeping Lovegrass	4 lbs.	2 lbs.	Pensacola Bahia	60 lbs.	30 lbs.
	Annual Lespedeza	40 lbs.	10 lbs.	Hulled Bermuda	10 lbs.	6 lbs.
				Sericea Lespedeza (2)	60 lbs.	--
April	Weeping Lovegrass	4 lbs.	2 lbs.	Pensacola Bahia	60 lbs.	30 lbs.
	Sudan Grass	60 lbs.	--	Weeping Lovegrass	6 lbs.	6 lbs.
		40 lbs.	10 lbs.	Hulled Bermuda	10 lbs.	6 lbs.
				Sericea Lespedeza (2)	60 lbs.	--
May	Weeping Lovegrass	4 lbs.	2 lbs.	Pensacola Bahia	60 lbs.	30 lbs.
	Sudan Grass	60 lbs.	--	Weeping Lovegrass	6 lbs.	6 lbs.
		40 lbs.	10 lbs.	Hulled Bermuda	10 lbs.	6 lbs.
				Sericea Lespedeza (2)	60 lbs.	--
June	Pearl Millet	50 lbs.	--	Pensacola Bahia	60 lbs.	30 lbs.
	Sudan Grass	60 lbs.	--	Hulled Bermuda	10 lbs.	6 lbs.
		40 lbs.	10 lbs.			
July	Pearl Millet	50 lbs.	--	Pensacola Bahia	60 lbs.	30 lbs.
	Sudan Grass	60 lbs.	--			
		40 lbs.	10 lbs.			
August	Pearl Millet	50 lbs.	--	Pensacola Bahia	60 lbs.	30 lbs.
	Rye	3 bu.	.5 bu.			
September	Rye grass	40 lbs.	--	Sericea Lespedeza (1)	75 lbs.	--
	Oats	4 bu.	1 bu.			
	Wheat	3 bu.	.5 bu.			
October	Rye grass	40 lbs.	--	Sericea Lespedeza (1)	75 lbs.	--
	Oats	4 bu.	1 bu.			
	Wheat	3 bu.	.5 bu.			
	Rye	3 bu.	.5 bu.			
	Barley	3 bu.	.5 bu.			
November	Rye grass	40 lbs.	--	Sericea Lespedeza (1)	75 lbs.	--
	Oats	4 bu.	1 bu.	Unhulled Bermuda	10 lbs.	6 lbs.
	Whe



NOTE: Use 36" D.O.T. approved fabric. Use wood or steel posts

SIDE VIEW


FRONT VIEW

SILT FENCE - TYPE NS

Non-Sensitive - Type A

NOT TO SCALE

Sd1-NS



TEMPORARY CONSTRUCTION EXIT

NOT TO SCALE

Co

CONCRETE WASHOUT AREA

PURPOSE - PREVENT OR REDUCE THE DISCHARGE OF POLLUTANTS TO STORM WATER FROM CONCRETE WASTE BY CONDUCTING WASHOUT OFFSITE, OR PERFORMING ONSITE WASHOUT IN A DESIGNATED AREA TO PREVENT POLLUTANTS FROM ENTERING SURFACE WATERS OR GROUNDWATER.

CONDITIONS OF USE - CONCRETE WASHOUT AREA BEST MANAGEMENT PRACTICES ARE IMPLEMENTED ON CONSTRUCTION PROJECTS WHERE:

- CONCRETE IS USED AS A CONSTRUCTION MATERIAL
- IT IS NOT POSSIBLE TO DISPOSE OF ALL CONCRETE WASTEWATER AND WASHOUT OFFSITE (READY MIX PLANT, ETC.).
- CONCRETE TRUCKS, PUMPERS, OR OTHER CONCRETE COATED EQUIPMENT ARE WASHED ONSITE.

DESIGN AND INSTALLATION SPECIFICATIONS

IMPLEMENTATION - THE FOLLOWING STEPS WILL HELP REDUCE STORMWATER POLLUTION FROM CONCRETE WASTES:

- PERFORM WASHOUT OF CONCRETE TRUCKS OFFSITE OR IN DESIGNATED CONCRETE WASHOUT AREAS ONLY.
- DO NOT WASH OUT CONCRETE TRUCKS ONTO THE GROUND, OR INTO STORM DRAINS, OPEN DITCHES, STREETS, OR STREAMS.
- DO NOT ALLOW EXCESS CONCRETE TO BE DUMPED ONSITE, EXCEPT IN DESIGNATED CONCRETE WASHOUT AREAS.
- CONCRETE WASHOUT AREAS MAY BE PREFABRICATED CONCRETE WASHOUT CONTAINERS, OR SELF-INSTALLED STRUCTURES (ABOVE-GRADE OR BELOW-GRADE).
- PREFABRICATED CONTAINERS ARE MOST RESISTANT TO DAMAGE AND PROTECT AGAINST SPILLS AND LEAKS. COMPANIES MAY OFFER DELIVERY SERVICE AND PROVIDE REGULAR MAINTENANCE AND DISPOSAL OF SOLID AND LIQUID WASTE.
- IF SELF-INSTALLED CONCRETE WASHOUT AREAS ARE USED, BELOW-GRADE STRUCTURES ARE PREFERRED OVER ABOVE-GRADE STRUCTURES BECAUSE THEY ARE LESS PRONE TO SPILLS AND LEAKS.
- SELF-INSTALLED ABOVE-GRADE STRUCTURES SHOULD ONLY BE USED IF EXCAVATION IS NOT PRACTICAL.

EDUCATION - THE FOLLOWING EDUCATION PRACTICES ARE RECOMMENDED:

- DISCUSS THE CONCRETE MANAGEMENT TECHNIQUES DESCRIBED IN THIS BEST MANAGEMENT PRACTICE WITH THE READY-MIX CONCRETE SUPPLIER BEFORE ANY DELIVERIES ARE MADE.
- EDUCATE EMPLOYEES AND SUBCONTRACTORS ON THE CONCRETE WASTE MANAGEMENT TECHNIQUES DESCRIBED IN THIS SECTION.
- ARRANGE FOR CONTRACTOR'S SUPERINTENDENT OR LEVEL 1A CERTIFIED PERSONNEL TO OVERSEE AND ENFORCE CONCRETE WASTE MANAGEMENT PROCEDURES.
- A SIGN SHOULD BE INSTALLED ADJACENT TO EACH TEMPORARY CONCRETE WASHOUT FACILITY TO INFORM CONCRETE EQUIPMENT OPERATORS TO UTILIZE THE PROPER FACILITIES.

CONTRACTS - INCORPORATE REQUIREMENTS FOR CONCRETE WASTE MANAGEMENT INTO CONCRETE SUPPLIER AND SUBCONTRACTOR AGREEMENTS.

LOCATION AND PLACEMENT - THE FOLLOWING GUIDELINES SHALL BE USED WHEN LOCATING AND PLACING THE CONCRETE WASH-OUT AREA:

- LOCATE WASHOUT AREA AT LEAST 50 FEET FROM SENSITIVE AREAS SUCH AS STORM DRAINS, OPEN DITCHES, OR WATER BODIES, INCLUDING WETLANDS.
- ALLOW CONVENIENT ACCESS FOR CONCRETE TRUCKS, PREFERABLY NEAR THE AREA WHERE THE CONCRETE IS BEING POURED.
- IF TRUCKS NEED TO LEAVE A PAVED AREA TO ACCESS WASHOUT, PREVENT TRACK-OUT WITH A CONSTRUCTION EXIT.
- THE NUMBER OF FACILITIES YOU INSTALL SHOULD DEPEND ON THE EXPECTED DEMAND FOR STORAGE CAPACITY.
- ON LARGE SITES WITH EXTENSIVE CONCRETE WORK, WASHOUTS SHOULD BE PLACED IN MULTIPLE LOCATIONS FOR EASE OF USE BY CONCRETE TRUCK DRIVERS.

ONSITE TEMPORARY CONCRETE WASHOUT FACILITY, TRANSIT TRUCK WASHOUT PROCEDURES:

- TEMPORARY CONCRETE WASHOUT FACILITIES SHALL BE LOCATED A MINIMUM OF 50 FT. FROM SENSITIVE AREAS INCLUDING STORM DRAIN INLETS, OPEN DRAINAGE FACILITIES, AND WATERCOURSES.
- CONCRETE WASHOUT FACILITIES SHALL BE CONSTRUCTED AND MAINTAINED IN SUFFICIENT QUANTITY AND SIZE TO CONTAIN ALL LIQUID AND CONCRETE WASTE GENERATED BY WASHOUT OPERATIONS.
  - APPROXIMATELY 7 GALLONS OF WASH WATER ARE USED TO WASH ONE TRUCK CHUTE.
  - APPROXIMATELY 50 GALLONS ARE USED TO WASH OUT THE HOPPER OF A CONCRETE PUMP TRUCK
- WASHOUT OF CONCRETE TRUCKS SHALL BE PERFORMED IN DESIGNATED AREAS ONLY.
- CONCRETE WASHOUT FROM CONCRETE PUMPER BINS CAN BE WASHED INTO CONCRETE PUMPER TRUCKS AND DISCHARGED INTO DESIGNATED WASHOUT AREA OR PROPERLY DISPOSED OF OFFSITE.
- ONCE CONCRETE WASTES ARE WASHED INTO THE DESIGNATED AREA AND ALLOWED TO HARDEN, THE CONCRETE SHOULD BE BROKEN UP, REMOVED, AND DISPOSED OF PER APPLICABLE SOLID WASTE REGULATIONS. DISPOSE OF HARDENED CONCRETE ON A REGULAR BASIS.

TEMPORARY ABOVE-GRADE CONCRETE WASHOUT FACILITY

- TEMPORARY CONCRETE WASHOUT FACILITY (TYPE ABOVE GRADE) SHOULD BE CONSTRUCTED AS SHOWN ON THE DETAILS WITH A RECOMMENDED MINIMUM LENGTH AND MINIMUM WIDTH OF 10 FT., BUT WITH SUFFICIENT QUANTITY AND VOLUME TO CONTAIN ALL LIQUID AND CONCRETE WASTE GENERATED BY WASHOUT OPERATIONS.
- PLASTIC LINING MATERIAL SHOULD BE A MINIMUM OF 10 MIL POLYETHYLENE SHEETING AND SHOULD BE FREE OF HOLES, TEARS, OR OTHER DEFECTS THAT COMPROMISE THE IMPERMEABILITY OF THE MATERIAL.

TEMPORARY BELOW-GRADE CONCRETE WASHOUT FACILITY


- TEMPORARY CONCRETE WASHOUT FACILITIES (TYPE BELOW GRADE) SHOULD BE CONSTRUCTED WITH A RECOMMENDED MINIMUM LENGTH AND MINIMUM WIDTH OF 10 FT. THE QUANTITY AND VOLUME SHOULD BE SUFFICIENT TO CONTAIN ALL LIQUID AND CONCRETE WASTE GENERATED BY WASHOUT OPERATIONS.
- PLASTIC LINING MATERIAL SHALL BE A MINIMUM OF 10 MIL POLYETHYLENE SHEETING AND SHOULD BE FREE OF HOLES, TEARS, OR OTHER DEFECTS THAT COMPROMISE THE IMPERMEABILITY OF THE MATERIAL.
- LINER SEAMS SHALL BE INSTALLED IN ACCORDANCE WITH MANUFACTURERS' RECOMMENDATIONS.
- SOIL BASE SHALL BE PREPARED FREE OF ROCKS OR OTHER DEBRIS THAT MAY CAUSE TEARS OR HOLES IN THE PLASTIC LINING MATERIAL.

INSPECTION AND MAINTENANCE


- INSPECT AND VERIFY THAT CONCRETE WASHOUT BMPS ARE IN PLACE PRIOR TO THE COMMENCEMENT OF CONCRETE WORK.
- DURING PERIODS OF CONCRETE WORK, INSPECT DAILY TO VERIFY CONTINUED PERFORMANCE.
- CHECK OVERALL CONDITION AND PERFORMANCE.
- CHECK REMAINING CAPACITY (% FULL).
- IF USING SELF-INSTALLED WASHOUT FACILITIES, VERIFY PLASTIC LINERS ARE INTACT AND SIDEWALLS ARE NOT DAMAGED.
- IF USING PREFABRICATED CONTAINERS, CHECK FOR LEAKS.
- WASHOUT FACILITIES SHALL BE MAINTAINED TO PROVIDE ADEQUATE HOLDING CAPACITY WITH A MINIMUM FREEBOARD OF 12 INCHES.
- WASHOUT FACILITIES MUST BE CLEANED, OR NEW FACILITIES MUST BE CONSTRUCTED AND READY FOR USE ONCE THE WASHOUT IS 75% FULL.
- IF THE WASHOUT IS NEARING CAPACITY, VACUUM AND DISPOSE OF THE WASTE MATERIAL IN AN APPROVED MANNER.
- DO NOT DISCHARGE LIQUID OR SLURRY TO WATERWAYS, STORM DRAINS OR DIRECTLY ONTO GROUND.
- DO NOT USE SANITARY SEWER WITHOUT LOCAL APPROVAL.
- PLACE A SECURE, NON-COLLAPSING, NON-WATER COLLECTING COVER OVER THE CONCRETE WASHOUT FACILITY PRIOR TO PREDICTED WET WEATHER TO PREVENT ACCUMULATION AND OVERFLOW OF PRECIPITATION.
- REMOVE AND DISPOSE OF HARDENED CONCRETE AND RETURN THE STRUCTURE TO A FUNCTIONAL CONDITION. CONCRETE MAY BE REUSED ONSITE OR HAULED AWAY FOR DISPOSAL OR RECYCLING.
- WHEN YOU REMOVE MATERIALS FROM THE SELF-INSTALLED CONCRETE WASHOUT, BUILD A NEW STRUCTURE; OR, IF THE PREVIOUS STRUCTURE IS STILL INTACT, INSPECT FOR SIGNS OF WEAKENING OR DAMAGE, AND MAKE ANY NECESSARY REPAIRS. RE-LINE THE STRUCTURE WITH NEW PLASTIC AFTER EACH CLEANING.

REMOVAL OF TEMPORARY CONCRETE WASHOUT FACILITIES


- WHEN TEMPORARY CONCRETE WASHOUT FACILITIES ARE NO LONGER REQUIRED FOR THE WORK, THE HARDENED CONCRETE, SLURRIES AND LIQUIDS SHALL BE REMOVED AND PROPERLY DISPOSED OF.
- MATERIALS USED TO CONSTRUCT TEMPORARY CONCRETE WASHOUT FACILITIES SHALL BE REMOVED FROM THE SITE OF THE WORK AND DISPOSED OF OR RECYCLED.
- HOLES, DEPRESSIONS OR OTHER GROUND DISTURBANCE CAUSED BY THE REMOVAL OF THE TEMPORARY CONCRETE WASHOUT FACILITIES SHALL BE BACKFILLED, REPAIRED, AND STABILIZED TO PREVENT EROSION.



WASHOUT STRUCTURE WITH WOOD PLANKS



EXCAVATED WASHOUT STRUCTURE



NOTE: CAN BE TWO STACKED BALES OR PARTIALLY EXCAVATED TO REACH 3 FT DEPTH

WASHOUT STRUCTURE WITH STRAW BALES

CONSTRUCTION SPECIFICATIONS

1. LOCATE WASHOUT STRUCTURE A MINIMUM OF 50 FEET AWAY FROM OPEN CHANNELS, STORM DRAIN INLETS, SENSITIVE AREAS, WETLANDS, BUFFERS AND WATER COURSES AND AWAY FROM CONSTRUCTION TRAFFIC.
2. SIZE WASHOUT STRUCTURE FOR VOLUME NECESSARY TO CONTAIN WASH WATER AND SOLIDS AND MAINTAIN AT LEAST 4 INCHES OF FREEBOARD. TYPICAL DIMENSIONS ARE 10 FEET X 10 FEET X 3 FEET DEEP.
3. PREPARE SOIL BASE FREE OF ROCKS OR OTHER DEBRIS THAT MAY CAUSE TEARS OR HOLES IN THE LINER. FOR LINER, USE 10 MIL OR THICKER UV RESISTANT, IMPERMEABLE SHEETING, FREE OF HOLES AND TEARS OR OTHER DEFECTS THAT COMPROMISE IMPERMEABILITY OF THE MATERIAL.
4. PROVIDE A SIGN FOR THE WASHOUT IN CLOSE PROXIMITY TO THE FACILITY.
5. KEEP CONCRETE WASHOUT STRUCTURE WATER TIGHT. REPLACE IMPERMEABLE LINER IF DAMAGED (E.G., RIPPED OR PUNCTURED). EMPTY OR REPLACE WASHOUT STRUCTURE THAT IS 75 PERCENT FULL, AND DISPOSE OF ACCUMULATED MATERIAL PROPERLY. DO NOT REUSE PLASTIC LINER. WET-VACUUM STORED LIQUIDS THAT HAVE NOT EVAPORATED AND DISPOSE OF IN AN APPROVED MANNER. PRIOR TO FORECASTED RAINSTORMS, REMOVE LIQUIDS OR COVER STRUCTURE TO PREVENT OVERFLOWS. REMOVE HARDENED SOLIDS, WHOLE OR BROKEN UP, FOR DISPOSAL OR RECYCLING. MAINTAIN RUNOFF DIVERSION AROUND EXCAVATED WASHOUT STRUCTURE UNTIL STRUCTURE IS REMOVED.

NOTE: WASHOUT OF THE CONCRETE TRUCK DRUM AT THE CONSTRUCTION SITE IS PROHIBITED

CONCRETE WASHDOWN AREA DETAIL

NOT TO SCALE

CSW

GEORGIA811.COM DIAL 811

THIS DRAWING MAY NOT BE REPRODUCED WITHOUT WRITTEN PERMISSION FROM MAVERICK ENGINEERING, LLC

THE CONTRACTOR SHOULD VERIFY ALL LOCATIONS, GRADES, AND DIMENSIONS ILLUSTRATED ON THE PLANS AND WILL REPORT ANY DISCREPANCIES TO MAVERICK ENGINEERING, LLC.

MAVERICK ENGINEERING, LLC.
205 GENE BLAND ROAD | JESUP, GA 31545
phone (912) 256-3704 www.maverickengineeringllc.com

SITE PLAN
HALL RICHARDS SENIOR CENTER


PARCEL NUMBER: JT-31, JT-32 & JT-33 JESUP, WAYNE COUNTY, GEORGIA

SHEET NAME: DETAILS

REVISIONS:
1.
2.
3.
4.
5.
6.
7.
8.
9.
10.

INITIAL DATE: 4/17/2025
DRAWN BY: BDP
CHECKED BY: BDP
PROJECT #: 2025-01

SHEET NUMBER: C 9.1



NOTE:BACKFILL

A. THE SOIL AT THE SIDES OF A PIPE AND ABOVE IT IS THE BACKFILL.
B. PRIOR TO BACKFILLING ANY EXCAVATION, ALL PIPING AND STRUCTURES, THE ENGINEER AND GOVERNING AUTHORITY'S INSPECTOR SHALL BE NOTIFIED FOR OBSERVATION.
C. AFTER PIPES HAVE BEEN TESTED AND APPROVED, BACKFILLING SHALL BE DONE WITH APPROVED MATERIAL FREE FROM LARGE CLODS OR STONES.
D. BACKFILL SHALL BE PLACED IN UNIFORM LAYERS, FOUR INCHES THICK, ON BOTH SIDES OF THE PIPE AND THOROUGHLY COMPACTED WITH PNEUMATIC OR HAND TAMPERS. THE BACKFILL SHALL BE BROUGHT UP UNIFORMLY ON BOTH SIDES OF THE PIPE AND COMPACTED TO AN ELEVATION OF ONE FOOT ABOVE THE TOP OF THE PIPE, AFTER WHICH THE FILL SHALL BE PLACED IN EIGHT INCH LIFTS. NO ROCK WILL BE ALLOWED IN THE BACKFILL WITHIN A DISTANCE OF ONE FOOT FROM THE PIPE, AND ROCK LARGER THAN SIX INCHES IN THE GREATEST DIMENSION WILL NOT BE PERMITTED IN ANY PART OF THE TRENCH OR BACKFILL.


1. BACKFILL SHALL BE COMPACTED TO NOT LESS THAN 95% OF THE MAXIMUM DRY WEIGHT PER CUBIC FOOT AS DETERMINED BY AASHTO METHOD T_99 (STANDARD PROCTOR TEST).
2. THE TOP 18 INCHES OF BACKFILL UNDER ANY PAVED AREA SHALL BE COMPACTED TO 100% STANDARD PROCTOR.
3. WATER SETTLING WILL NOT BE PERMITTED IN CLAY SOILS. IT MAY BE ALLOWED AT THE OPTION OF THE GOVERNING AUTHORITY'S INSPECTOR AND DESIGN ENGINEER IN SANDY SOILS

NOTE:WATER MAIN 36" BURY MINIMUM.


NOTE: PIPE BEDDING

A. THE CONTACT BETWEEN A PIPE AND THE FOUNDATION ON WHICH IT RESTS IS THE PIPE BEDDING.
B. CLASSES OF BEDDING: FOUR TYPICAL CLASSES OF BEDDING TO BE USED FOR PIPES IN TRENCHES ARE DESCRIBED AS FOLLOWS:
   1. CLASS A _ CONCRETE CRADLE OR CONCRETE ARCH BEDDING: THIS CLASS OF BEDDING MAY TAKE EITHER OF TWO FORMS.
      a. CONCRETE CRADLE_ THE PIPE SHALL BE BEDDED IN A MONOLITHIC CRADLE OF PLAIN OR REINFORCED CONCRETE HAVING A MINIMUM THICKNESS OF 1/4 THE INSIDE PIPE DIAMETER OF A MINIMUM OF 4 INCHES UNDER THE BARREL AND EXTENDING UP THE SIDES FOR A HEIGHT EQUAL TO 1/4 THE OUTSIDE DIAMETER. THE CRADLE SHALL HAVE WIDTH AT LEAST EQUAL TO THE OUTSIDE DIAMETER OF THE PIPE BARREL PLUS 8 INCHES. BACKFILL ABOVE THE CRADLE AND EXTENDING TO 12 INCHES ABOVE THE CROWN OF THE PIPE SHALL BE COMPACTED CAREFULLY.
      b. CONCRETE ARCH– THE PIPE SHALL BE EMBEDDED IN A CAREFULLY COMPACTED GRANULAR MATERIAL HAVING A MINIMUM THICKNESS OF 1/4 THE OUTSIDE DIAMETER BETWEEN BARREL AND BOTTOM OF TRENCH EXCAVATION AND EXTENDING HALFWAY UP THE SIDES OF THE PIPE. THE TOP HALF OF THE PIPE SHALL BE COVERED WITH MONOLITHIC PLAIN OR REINFORCED CONCRETE ARCH HAVING A MINIMUM THICKNESS OF 1/4 THE INSIDE DIAMETER AT THE CROWN AND HAVING A MINIMUM WIDTH EQUAL TO THE OUTSIDE PIPE DIAMETER PLUS 8 INCHES.
   2. CLASS B_ FIRST _ CLASS BEDDING _ CLASS B BEDDING MAY BE ACHIEVED BY EITHER OF TWO CONSTRUCTION METHODS.
      a. SHAPED BOTTOM WITH TAMPED BACKFILL. THE BOTTOM OF THE TRENCH EXCAVATION SHALL BE SHAPED TO CONFORM TO A CYLINDRICAL SURFACE WITH A RADIUS AT LEAST 2 INCHES GREATER THAN THE RADIUS TO THE OUTSIDE OF THE PIPE AND WITH A WIDTH SUFFICIENT TO ALLOW 6/10 OF THE WIDTH OF THE PIPE BARREL TO BE BEDDED IN FINE GRANULAR FILL PLACED IN THE SHAPED EXCAVATION. CAREFULLY COMPACTED BACKFILL SHALL BE PLACED AT THE SIDES OF THE PIPE TO A THICKNESS OF AT LEAST 12 INCHES ABOVE THE TOP OF THE PIPE. SHAPED TRENCH BOTTOMS SHALL BE USED ONLY WITH THE APPROVAL OF THE ENGINEER.
      b. COMPACTED GRANULAR BEDDING WITH TAMPED BACKFILL. THE PIPE SHALL BE BEDDED IN COMPACTED GRANULAR MATERIAL PLACED ON A FLAT TRENCH BOTTOM. THE GRANULAR BEDDING SHALL HAVE A MINIMUM THICKNESS OF 1/4 THE OUTSIDE PIPE DIAMETER AND SHALL EXTEND HALFWAY UP THE PIPE BARREL AT THE SIDES. THE REMAINDER OF THE SIDE FILLS AND MINIMUM DEPTH OF 12 INCHES OVER THE TOP OF THE PIPE SHALL BE FILLED WITH CAREFULLY COMPACTED, SELECT MATERIAL.
   3. CLASS C _ ORDINARY BEDDING: CLASS C ORDINARY BEDDING MAY BE ACHIEVED BY EITHER OF TWO CONSTRUCTION METHODS:
      a. SHAPED BOTTOM. THE PIPE SHALL BE BEDDED WITH "ORDINARY" CARE IN AN EARTH FOUNDATION FORMED IN THE TRENCH BOTTOM BY A SHAPED EXCAVATION WHICH WILL FIT THE PIPE BARREL WITH REASONABLE CLOSENESS FOR A WIDTH OF AT LEAST 50% OF THE OUTSIDE PIPE DIAMETER. THE SIDE FILLS AND AREA OVER THE PIPE TO A MINIMUM DEPTH OF 6 INCHES ABOVE THE TOP OF THE PIPE SHALL BE FILLED WITH LIGHTLY COMPACTED FILL. THE SHAPED BOTTOM BEDDING SHALL BE USED ONLY WITH THE APPROVAL OF THE ENGINEER.
      b. COMPACTED GRANULAR BEDDING WITH A TAMPED BACKFILL. THE PIPE SHALL BE BEDDED IN COMPACTED GRANULAR MATERIAL PLACED ON A FLAT TRENCH BOTTOM. THE GRANULAR BEDDING SHALL HAVE A MINIMUM THICKNESS OF 4 INCHES UNDER THE BARREL AND SHALL EXTEND 1/10 TO 1/6 OF THE OUTSIDE DIAMETER UP THE PIPE BARREL AT THE SIDES. THE REMAINDER OF THE SIDE FILLS AND TO A MINIMUM DEPTH OF 6 INCHES OVER THE TOP OF THE PIPE SHALL BE FILLED WITH LIGHTLY COMPACTED BACKFILL.
   4. CLASS D _ CLASS D BEDDING IS NOT PERMISSIBLE. FLAT BOTTOM TRENCH. IN THIS CLASS OF BEDDING THE BOTTOM IS LEFT FLAT, AND NO CARE IS TAKEN TO SECURE COMPACTION OF BACKFILL AT THE SIDES IMMEDIATELY OVER THE PIPE.
C. GRANULAR PIPE BEDDING MATERIAL SHALL BE WELL GRADED CRUSHED STONE OR CRUSHED GRAVEL MEETING THE REQUIREMENTS OF ASTM C33, GRADATION 67 (3/4 INCH TO NO. 4). A WELL_GRADED GRAVEL MEETING THESE SAME REQUIREMENTS CAN ALSO BE USED.
D. WHERE LEDGE ROCK, COMPACT ROCKY OR GRAVELLY SOIL, OR OTHER UNYIELDING FOUNDATION MATERIAL IS ENCOUNTERED, THE PIPES SHALL BE BEDDED IN ACCORDANCE WITH THE REQUIREMENTS OF THE FOREGOING CLASSES OF BEDDING, BUT WITH THE FOLLOWING ADDITIONS: THE HARD UNYIELDING MATERIAL SHALL BE EXCAVATED TO THE ELEVATION OF THE BOTTOM OF THE CONCRETE CRADLE (CLASS A BEDDING) OR BELOW THE BOTTOM OF THE PIPE AND THE PIPE BELL (CLASS B OR C BEDDING), TO DEPTH OF AT LEAST 6 INCHES (15CM). THE WIDTH OF THE EXCAVATION SHALL BE AT LEAST 5/4 THE OUTSIDE DIAMETER OF THE PIPE AND IT SHALL BE REFILLED WITH GRANULAR MATERIAL AS IDENTIFIED ABOVE.


PIPE BEDDING



PLAN




PLAN



SECTION A-A

PIPE OUTLET TO WELL DEFINED CHANNEL




SECTION A-A

PIPE OUTLET TO FLAT AREA
NO WELL DEFINED CHANNEL

NOTES:
1. La IS THE LENGTH OF THE REPRAP APRON.
2. D = 1.5 TIMES THE MAXIMUM STONE DIAMETER BUT NOT LESS THAN 6".
3. IN A WELL-DEFINED CHANNEL, EXTEND TO APRON UP THE CHANNEL BANKS TO AN ELEVATION OF 6" ABOVE THE MAXIMUM TAIL WATER DEPTH OR TO THE TOP OF THE BANK (WHICHEVER IS LESS).
4. A FILTER BLANKET OR FILTER FABRIC SHOULD BE INSTALLED BETWEEN THE RIPRAP AND THE SOIL FOUNDATION

RIPRAP OUTLET PROTECTION (St)
NOT TO SCALE



NOTES:
1. LENGTH OF RESTRAINT SHOWN IS IN FEET. FITTING DIAMETERS ARE IN INCHES.
2. WHERE LINES CONSIST OF BOTH DUCTILE IRON AND PVC WITHIN THE LIMITS OF REQUIRED RESTRAINT, LIMITS FOR PVC SHALL APPLY.
3. U1 AND U2 = UNINTERUPTED STRAIGHT RUNS OF PIPE IN EACH DIRECTION.
4. Ur = THE SMALLER OF U1 OR U2
5. L = MINIMUM RESTRAINED LENGTH ALONG THE BRANCH.
6. WHERE Ur IS LESS THAN 5', RESTRAIN TEE AS A 90°. HORIZONTAL BEND.
7. INFORMATION IN THE TABLES ABOVE ARE BASED ON THE DESIGN INFORMATION SHOWN. THE ENGINEER SHALL PROVIDE AMENDED RESTRAINT LENGTHS IF SITE CONDITIONS DIFFER


PVC LINE

TEE \ Ur	5'–10'	11'–20'	21'–35'	> 35'
4X4	43	28	4	*
6X4	38	17	*	*
6X6	64	49	25	*
8X4	34	6	*	*
8X6	61	42	10	*
8X8	87	72	48	12
10X4	29	*	*	*
10X6	58	34	*	*
10X8	84	66	35	*
10X10	106	91	67	31
12X4	24	*	*	*
12X6	54	26	*	*
12X8	82	60	23	*
12X10	104	86	57	13
12X12	126	112	87	51

MINIMUM RESTRAINED LENGTH (L)

*RESTRAIN AT TEE ONLY.

TEE RESTRAINT (PVC PIPE)
N.T.S.



PVC LINE

PIPE DIA.	BEND ANGLE 11 1/4°	22 1/2°	45°	90°
4	2	4	8	18
6	3	5	11	25
8	4	7	14	33
10	4	8	16	39
12	5	9	19	45
16	5	9	19	45
20	6	11	23	54
24	8	16	26	62


DUCTILE IRON LINE

PIPE DIA.	BEND ANGLE 11 1/4°	22 1/2°	45°	90°
4	3	5	9	20
6	3	6	12	28
8	4	8	16	36
10	5	9	19	43
12	6	11	22	51
16	7	14	28	65
20	8	16	33	79
24	9	19	38	92

MINIMUM RESTRAINED LENGTH (L)

NOTES:
1. LENGTH OF RESTRAINT SHOWN IS IN FEET. PIPE DIAMETERS ARE IN INCHES.
2. WHERE LINES CONSIST OF BOTH DUCTILE IRON AND PVC WITHIN THE LIMITS OF REQUIRED RESTRAINT, LIMITS FOR PVC SHALL APPLY.
3. INFORMATION IN THE TABLES ABOVE ARE BASED ON THE DESIGN INFORMATION SHOWN. THE ENGINEER SHALL PROVIDE AMENDED RESTRAINT LENGTHS IF SITE CONDITIONS DIFFER

HORIZONTAL BEND RESTRAINT
N.T.S.



POLYETHYLENE WRAPPED DUCTILE IRON LINE


PIPE DIA.	L
4	58
6	82
8	107
10	128
12	151
16	193
20	234
24	273

PVC LINE

PIPE DIA.	L
4	39
6	55
8	72
10	87
12	102
16	131
20	159
24	185

NOTES:
1. LENGTH OF RESTRAINT SHOWN IS IN FEET. FITTING DIAMETERS ARE IN INCHES.
2. WHERE LINES CONSIST OF BOTH DUCTILE IRON AND PVC WITHIN THE LIMITS OF REQUIRED RESTRAINT, LIMITS FOR PVC SHALL APPLY.
3. FOR LINE STUBS (SEE DETAIL W34), THE LENGTH OF RESTRAINT (L) SHALL BE FROM THE VALVE AND NOT THE CAP.
4. INFORMATION IN THE TABLES ABOVE ARE BASED ON THE DESIGN INFORMATION SHOWN. THE ENGINEER SHALL PROVIDE AMENDED RESTRAINT LENGTHS IF SITE CONDITIONS DIFFER

DEAD END RESTRAINT
N.T.S.



PVC LINE

PIPE DIA.	BEND ANGLE 11 1/4° Lu	LL	22 1/2° Lu	LL	45° Lu	LL
4	4	1	8	2	17	3
6	6	1	11	2	23	4
8	8	2	15	3	30	6
10	9	2	18	4	36	7
12	11	2	21	4	43	8
16	10	3	21	5	42	10
20	13	3	25	6	51	12
24	15	4	29	7	60	15

POLYETHELYNE WRAPPED DUCTILE IRON LINE

PIPE DIA.	BEND ANGLE 11 1/4° Lu	LL	22 1/2° Lu	LL	45° Lu	LL
4	6	1	12	2	24	4
6	9	2	17	3	34	5
8	11	2	22	3	45	7
10	13	2	26	4	53	8
12	15	3	30	5	63	9
16	19	3	39	6	80	12
20	23	4	47	7	97	15
24	27	4	55	8	113	17

NOTES:
1. LENGTH OF RESTRAINT SHOWN IS IN FEET. PIPE DIA. IS IN INCHES
2. WHERE LINES CONSIST OF BOTH DUCTILE IRON AND PVC WITHIN THE LIMITS OF REQUIRED RESTRAINT, LIMITS FOR PVC SHALL APPLY.
3. INFORMATION IN THE TABLES ABOVE ARE BASED ON THE DESIGN INFORMATION SHOWN. THE ENGINEER SHALL PROVIDE AMENDED RESTRAINT LENGTHS IF SITE CONDITIONS DIFFER

VERTICAL BEND RESTRAINT
N.T.S.

MAVERICK ENGINEERING, LLC.
205 GENE BLAND ROAD | JESUP, GA 31545
phone (912) 256-3704 www.maverickengineeringllc.com

GEORGIA811.COM DIAL 811

THIS DRAWING MAY NOT BE REPRODUCED WITHOUT WRITTEN PERMISSION FROM MAVERICK ENGINEERING, LLC

THE CONTRACTOR SHOULD VERIFY ALL LOCATIONS, GRADES, AND DIMENSIONS ILLUSTRATED ON THE PLANS AND WILL REPORT ANY DISCREPANCIES TO MAVERICK ENGINEERING, LLC.

SITE PLAN
HALL RICHARDS SENIOR CENTER


PARCEL NUMBER: JT-31, JT-32 & JT-33 JESUP, WAYNE COUNTY, GEORGIA

SHEET NAME:
DETAILS

REVISIONS:
1.
2.
3.
4.
5.
6.
7.
8.
9.
10.

INITIAL DATE: 4/17/2025
DRAWN BY: BDP
CHECKED BY: BDP
PROJECT #: 2025-01


SHEET NUMBER:
C 9.3



PLAN VIEW


TAPPING SLEEVE DETAIL

N.T.S.




VALVE BOX DETAIL

N.T.S.



SEWER SERVICE CLEAN-OUT DETAIL

NOT TO SCALE




NOTES:

1. TAPPING SADDLE TO BE DUCTILE IRON WITH TYPE 304 STAINLESS STEEL FORGED DOUBLE STRAPS, STAINLESS STEEL BOLTS, NUTS, AND WASHERS. FINISH IS FUSION BONDED EPOXY TO AVERAGE THICKNESS OF 12MILS.
2. ALL 1" AND 2" TAPS ON WATER LINES SMALLER THAN 6"(SIX INCHES) WILL REQUIRE A TAPPING SADDLE; ALL TWO INCH (2") TAPS WILL REQUIRE A TAPPING SADDLE, REGARDLESS OF WATER MAIN SIZE.
3. A VALVE BOX SHALL BE USED FOR 2" CORPORATION STOPS.(SEE DETAIL W4)

1" & 2" WATER TAPPING SADDLE

N.T.S.



NOTES:

THE SEPARATION OF WATER MAINS AND SEWERS SHALL COMPLY WITH THE GEORGIA ENVIRONMENTAL PROTECTION DIVISION MINIMUM STANDARDS FOR PUBLIC WATER SYSTEMS, WHICH ARE GENERALLY AS FOLLOWS:

A. PARALLEL INSTALLATION:


1. NORMAL CONDITIONS: THE INSIDE EDGE OF A WATER LINE SHALL BE LAID AT LEAST 10 FEET HORIZONTALLY FROM THE INSIDE EDGE OF ANY SANITARY SEWER, STORM SEWER OR SEWER MANHOLE.
2. UNUSUAL CONDITIONS: WHEN LOCAL CONDITIONS PREVENT A HORIZONTAL SEPARATION OF 10 FEET, AND WHEN APPROVED BY THE ENGINEER, THE INSIDE EDGE OF A WATER MAIN MAY BE LAID A MINIMUM OF 5 FEET FROM THE INSIDE EDGE OF A SEWER PROVIDED THAT THE BOTTOM OF THE WATER MAIN IS AT LEAST 18 INCHES HIGHER THAN THE TOP OF THE SEWER (SEE DETAIL), AND THE WATER MAIN IS LAID IN A SEPARATE TRENCH OR ON AN UNDISTURBED EARTH SHELF.

B. CROSSINGS:

1. NORMAL CONDITIONS: WHENEVER POSSIBLE, THE BOTTOM OF THE WATER MAIN SHALL BE AT LEAST 18 INCHES HIGHER THAN THE TOP OF THE SEWER.
2. UNUSUAL CONDITIONS: IF A WATER MAIN MUST CROSS UNDER A SEWER, THE TOP OF THE WATER MAIN SHALL BE AT LEAST 18 INCHES LOWER THAN THE BOTTOM OF THE SEWER, THE WATER MAIN PIPE SHALL BE CENTERED AT THE CROSSING SO THAT THE JOINTS ARE EQUIDISTANT AND AS FAR AS POSSIBLE FROM THE SEWER, AND ADEQUATE STRUCTURAL SUPPORT SHALL BE PROVIDED FOR THE SEWER TO PREVENT EXCESSIVE DEFLECTION OF THE SEWER AT THE CROSSING. ADEQUATE STRUCTURAL SUPPORT SHALL INCLUDE BACKFILLING THE ENTIRE UTILITY CROSSING AREA WITH 3/4" CRUSHED STONE AS SHOWN IN THE DETAIL.

MINIMUM WATER AND SEWER PIPE SEPARATION REQUIREMENTS

N.T.S.



MATERIALS		
ITEM	QUAN.	DESCRIPTION
1	1	WATER METER
2	1	DOUBLE CHECK VALVE ASSEMBLY *
3	2	METER BOX (JUMBO METER BOX FOR 5/8", 3/4", 1" & 1 1/2" BFD ONLY)
4	4	TEST COCKS
5	2	FULL PORT BALL VALVES
6		POLYETHYLENE, COPPER OR BRASS CUT TO LENGTH
7	2	UNION BRASS
8	1	CURB STOP

* DUAL CHECK VALVES ARE NOT ALLOWABLE

INSTALLATION INSTRUCTIONS:

THE ASSEMBLY SHALL NOT BE BURIED IN EARTH, BUT MAY BE INSTALLED IN A UTILITY BOX ADJACENT TO OR AS CLOSE AS PRACTICAL TO, THE OUTLET SIDE OF THE METER. UNDER NO CONDITION WILL ANY CONNECTION BE ALLOWED BETWEEN THE SERVICE METER AND A BACKFLOW PREVENTER USED FOR SYSTEM CONTAINMENT.


NOTES:

1. FOR FINAL APPROVAL, ASSEMBLY MUST BE CENTERED IN ENCLOSURE. INSTALLER MUST PROVIDE FOR THERMAL EXPANSION DOWNSTREAM OF THE BACKFLOW PREVENTOR.
2. IF A PRESSURE MONITOR IS TO BE INSTALLED, ADD A TEE, VALVE, FITTINGS AND MOUNT ON SUPPLY SIDE PRIOR TO BACKFLOW PREVENTION DEVICE; UNDER NO CIRCUMSTANCES SHALL THE TEST PORTS BE MODIFIED OR UTILIZED FOR THIS OR OTHER APPLICATION, OTHER THAN BACKFLOW DEVICE TESTING.
3. WHEN INSTALLED WITHIN PEDESTRIAN TRAFFIC/SIDEWALK AREAS CAST IRON OR QUAZITE SHALL BE USED.

(5/8", 3/4", 1", & 1 1/2" SIZES)

WATER METER & DOUBLE CHECK VALVE ASSEMBLY

NOT TO SCALE



NOTE:
ALL FITTINGS IN LATERAL SHALL BE LOW-LEAD BRASS COMPRESSION TYPE.

WATER SERVICE LATERAL (6" OR LARGER MAIN)

NOT TO SCALE

GEORGIA811.COM DIAL 811

THIS DRAWING MAY NOT BE REPRODUCED WITHOUT WRITTEN PERMISSION FROM MAVERICK ENGINEERING, LLC

THE CONTRACTOR SHOULD VERIFY ALL LOCATIONS, GRADES, AND DIMENSIONS ILLUSTRATED ON THE PLANS AND WILL REPORT ANY DISCREPANCIES TO MAVERICK ENGINEERING, LLC.

MAVERICK ENGINEERING, LLC.
205 GENE BLAND ROAD | JESUP, GA 31545
phone (912) 256-3704 www.maverickengineeringllc.com

SITE PLAN
HALL RICHARDS SENIOR CENTER


PARCEL NUMBER: JT-31, JT-32 & JT-33 JESUP, WAYNE COUNTY, GEORGIA

SHEET NAME:
DETAILS

REVISIONS:
1.
2.
3.
4.
5.
6.
7.
8.
9.
10.


INITIAL DATE: 4/17/2025
DRAWN BY: BDP
CHECKED BY: BDP
PROJECT #: 2025-01

SHEET NUMBER:
C 9.4




NOTES:
1. COMPACT SUBGRADE TO 95% STANDARD PROCTOR.
2.INSTALL EXPANSION JOINTS EVERY 20'.
3. USE 3000 PSI CONCRETE WITH FIBER OR 4"X4" WELDED WIRE MESH


FLUME DETAIL
N.T.S.




EXPANSION JOINT
N.T.S.



WALK CONTROL JOINT
N.T.S.




HEAVY DUTY PAVEMENT SECTION
N.T.S.



NOTE:
6" GRADED AGGREGATE BASE TO BE EXTENDED A MINIMUM OF 4" THE EDGE OF ALL PAVEMENT.

TYPICAL PAVEMENT SECTION
N.T.S.



NOTES:

1. HANDICAP RAMP CONSTRUCTION SHALL CONFORM TO ALL FEDERAL, STATE AND LIBERTY COUNTY CODES AND SPECIFICATIONS.

2. SURFACES SHALL MEET THE GUIDELINES OF THE ADA STANDARDS FOR ACCESSIBILITY, APPENDIX A, PART 36.


3. WHERE SIDEWALK IS FLUSH WITH BACK OF CURB, DELETE ADDITIONAL 4' CONCRETE SIDEWALK AND TRANSITION THE CURB AND SIDEWALK SUCH THAT THE MAXIMUM SLOPE OF THE RAMP AND TRANSITION SIDEWALK IS 1:12.

4. THE FLARED SIDES MUST HAVE A 1:10 SLOPE. IF THE DISTANCE X IS LESS THAN 48", THEN THE SLOPE OF THE FLARED SIDES SHALL NOT EXCEED 1:12.


5. THE SLOPE OF THE GUTTER MUST NOT EXCEED 1:20 ADJACENT TO THE RAMP.

6. DETECTABLE WARNING SHALL CONSIST OF RAISED TRUNCATED DOMES WITH A DIAMETER OF NOMINAL 0.9 INCHES, A HEIGHT OF NOMINAL 0.2 INCHES AND A CENTER TO CENTER SPACING OF NOMINAL 2.35 INCHES AND SHALL CONTRAST VISUALLY WITH ADJOINING SURFACES. IF THE SIDEWALK AND RAMP ARE CONSTRUCTED OF CONCRETE, THE WARNING AREA SHALL BE RED BRICK IN COLOR. IF THE SIDEWALK AND RAMP ARE CONSTRUCTED OF RED BRICK, THE WARNING AREA SHALL BE GRAY IN COLOR. THE COLOR USED TO PROVIDE CONTRAST SHALL BE AN INTEGRAL PART OF THE WALKING SURFACE.

7. BRICK PAVERS SHALL BE SET IN A WET MORTAR BED. THE BED SHALL BE PLACED ON CONCRETE. THE CONCRETE SHALL BE A MINIMUM OF FOUR INCHES THICK.



ISOMETRIC VIEW OF RAMP




SECTION A-A

DETECTABLE WARNING DETAIL

NOTES:
1. HANDICAP RAMP CONSTRUCTION SHALL CONFORM TO ALL FEDERAL, STATE AND HINESVILLE CODES AND SPECIFICATIONS.
2. SURFACES SHALL MEET THE GUIDELINES OF THE ADA STANDARDS FOR ACCESSIBILITY, APPENDIX A, PART 36.
3. THE SLOPE OF THE GUTTER MUST NOT EXCEED 1:20 ADJACENT TO THE RAMP.
4. DETECTABLE WARNINGS SHALL CONSIST OF RAISED TRUNCATED DOMES WITH A DIAMETER OF NOMINAL 0.9 INCHES. A HEIGHT OF NORMAL 0.2 INCHES AND A CENTER TO CENTER SPACING OF NOMINAL 2.35 INCHES CONSTRUCTION OF CONCRETE. THE WARNING AREA SHALL BE RED BRICK IN COLOR. IF THE SIDEWALK AND RAMP ARE CONSTRUCTED OF RED BRICK, THE WARNING AREA SHALL BE GRAY IN COLOR. THE COLOR USED TO PROVIDE CONTRAST SHALL BE AN INTEGRAL PART OF THE WALKING SURFACE.

HANDICAP RAMP DETAIL
N.T.S.




NOTE:

SIGNAGE SHALL CONFORM TO ALL APPLICABLE FEDERAL, STATE AND LIBERTY COUNTY CODES AND SPECIFICATIONS.

HANDICAP SIGN

STANDARD CONSTRUCTION DETAILS
HANDICAP PARKING SIGN DETAIL
N.T.S



NOTE:

1. STRIPING AND CONSTRUCTION SHALL CONFORM TO ALL APPLICABLE FEDERAL AND STATE REGULATIONS.

2. ALL PAVEMENT MARKINGS AND STRIPING IN THE RIGHT-OF-WAY SHALL BE THERMOPLASTIC.

STANDARD CONSTRUCTION DETAILS
ADA HANDICAP PARKING SPACE STRIPING DETAIL
N.T.S

GEORGIA811.COM DIAL 811

THIS DRAWING MAY NOT BE REPRODUCED WITHOUT WRITTEN PERMISSION FROM MAVERICK ENGINEERING, LLC

THE CONTRACTOR SHOULD VERIFY ALL LOCATIONS, GRADES, AND DIMENSIONS ILLUSTRATED ON THE PLANS AND WILL REPORT ANY DISCREPANCIES TO MAVERICK ENGINEERING, LLC.

MAVERICK ENGINEERING, LLC.
205 GENE BLAND ROAD | JESUP, GA 31545
phone (912) 256-3704 www.mavrickengineeringllc.com

SITE PLAN
HALL RICHARDS SENIOR CENTER


PARCEL NUMBER: JT-31, JT-32 & JT-33 JESUP, WAYNE COUNTY, GEORGIA

SHEET NAME:
DETAILS

REVISIONS:
1.
2.
3.
4.
5.
6.
7.
8.
9.
10.


INITIAL DATE: 4/17/2025
DRAWN BY: BDP
CHECKED BY: BDP
PROJECT #: 2025-01

SHEET NUMBER:
C 9.5




TYPICAL DITCH DETAIL

N.T.S.



DUMPSTER AREA PLAN VIEW


N.T.S.



ELEVATION DUMPSTER

DUMPSTER ENCLOSURE GATE

N.T.S.



DUMPSTER ENCLOSURE WALL

N.T.S.

GEORGIA811.COM DIAL 811

THIS DRAWING MAY NOT BE REPRODUCED WITHOUT WRITTEN PERMISSION FROM MAVERICK ENGINEERING, LLC

THE CONTRACTOR SHOULD VERIFY ALL LOCATIONS, GRADES, AND DIMENSIONS ILLUSTRATED ON THE PLANS AND WILL REPORT ANY DISCREPANCIES TO MAVERICK ENGINEERING, LLC.

MAVERICK ENGINEERING, LLC.
205 GENE BLAND ROAD | JESUP, GA 31545
phone (912) 256-3704 www.mavrickengineeringllc.com

SITE PLAN
HALL RICHARDS SENIOR CENTER

PARCEL NUMBER: JT-31, JT-32 & JT-33 JESUP, WAYNE COUNTY, GEORGIA

SHEET NAME:
DETAILS

REVISIONS:
1.
2.
3.
4.
5.
6.
7.
8.
9.
10.

INITIAL DATE: 4/17/2025
DRAWN BY: BDP
CHECKED BY: BDP
PROJECT #: 2025-01

SHEET NUMBER:
C 9.6