Town of Richmond, Rhode Island

Bid specifications for **GAS FURNACES** be located at the Richmond Public Works Building, 51 Buttonwoods Road, Wyoming, Rhode Island.

The bidder agrees to supply **all materials and labor** necessary to complete the entire project. Upon bid award, the contractor will order the necessary supplies and install in a timely manner.

1) Install first floor high efficiency gas furnace with new evaporator and condenser. Approximately 100,000 BTU, with 5-ton evaporator coils and condensers and new refrigerant lines.
2) Install second floor high efficiency gas furnace with new evaporator and condenser. Approximately 100,000 BTU, with 5-ton evaporator coils and condensers and new refrigerant lines.
3) Successful bidder will be required to remove all existing components. DPW will dispose of all items.
4) Bidders are permitted to view the site. Contact DPW Director Gary Robar at 401-539-8474 or dpw@richmondri.com to schedule an appointment.
5) As required by RI General Laws, this is a prevailing wage project. As such, certified weekly payrolls must be submitted by all contractors, subcontractors and subrecipients.
6) The Town reserves the right to award one or both projects depending on the total cost.
7) Bids shall be submitted on the attached form.

Please include submittals that include specifications on materials used.

Any addenda to this solicitation will be posted on our website at https://www.richmondri.com/Bids.aspx