city of greenville

MEMORANDUM

Date: October 30, 2026

To: All Prospective Respondents

From: Rod Gray, Purchasing Administrator
City of Greenville Purchasing Division

Project: Lighting Upgrade for One City Plaza Parking Garage

RFP No: 27-4028

Addendum Number 1

This Addendum forms a part of the Contract Documents and modifies the original Solicitation Documents dated October 15, 2026. **Acknowledge receipt of this Addendum No. 1 in the space provided on the Signature Form.**

The above-mentioned RFP is hereby amended and/or supplemented by the following:

Question: It appears that the (100) additional new fixtures will be tied into the existing lighting circuits of the 110 fixtures, and conduits will be surface mounted. What is the maximum distance anticipated for a new conduit for each fixture? 20FT, 30FT etc.?

Answer: The maximum should be 50 ft from each light; however, it is recommended that you do a site visit to do a full determination of the conduit needed to meet the requirements of this job

Question: Is the existing parking garage post tension construction or standard rebar and is there any requirement for X-Ray for anchor placement?

Answer: It is post tension, as it was a pour in place garage. There would not be a need to x-ray as the anchors should only be ¾ inch.

Question: Is this project prevailing wage (Davis Bacon)?

Answer: No.

Question: Is there a spec sheet for the city provided LED vapor tight fixtures available and can that be provided to us?

Answer: It will be posted to the website.

https://www.greenvillesc.gov/bids-requests-for-proposals

Question: Has a lighting layout been prepared to identify the locations for the installation of the fixtures that are being added?

Answer: We have established tentative locations and they will posted to the website.

https://www.greenvillesc.gov/bids-requests-for-proposals

Question: Will the existing 6 lamp LED vapor lights (located at the Richardson St entrance/exit) be replaced?

Answer: No.

End of Addendum Number 1