BID FORM - CHICAGO STREET COMBINED SEWER SEPARATION PROJECT
BID 26-036

BASE BID

		CODED PAY ITEMS				
1.00	**PAY ITEM #**	**EARTHWORK & EROSION CONTROL**	**UNITS**	**QUANTITY**	**UNIT COST**	**COST**
1.01	20100210	TREE REMOVAL OVER 15"	UNIT	28	$	$
1.02	21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	1,352	$	$
1.03	25000350	SEEDING, CLASS 7	ACRE	0.25	$	$
1.04	25000400	NITROGEN FERTILIZER NUTRIENT	POUND	204	$	$
1.05	25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	204	$	$
1.06	25100105	MULCH, METHOD 1	ACRE	0.25	$	$
1.07	25200110	SODDING, SALT TOLERANT	SQ YD	1,352	$	$
1.08	25200200	SUPPLEMENTAL WATERING	UNIT	102	$	$
1.09	28000510	INLET FILTERS	EACH	59	$	$
1.10	Z0077700	WOOD FENCE TO BE REMOVED AND RE-ERECTED	FOOT	13	$	$
1.11		LANDSCAPING SPECIAL	EACH	10	$	$
1.12	X0326806	WASHOUT BASIN	L SUM	1	$	$
1.00		**Sub-Total**				**$**

		CODED PAY ITEMS				
2.00	**PAY ITEM #**	**PAVEMENT**	**UNITS**	**QUANTITY**	**UNIT COST**	**COST**
2.01	31101200	SUBBASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	346	$	$
2.02	31102300	SUBBASE GRANULAR MATERIAL, TYPE C 6"	SQ YD	6,611	$	$
2.03	35101582	AGGREGATE BASE COURSE, TYPE B 2"	SQ YD	606	$	$
2.04	35101600	AGGREGATE BASE COURSE, TYPE B 4"	SQ YD	168	$	$
2.05	40600275	BITUMINOUS MATERIALS (PRIME COAT)	POUND	9,355	$	$
2.06	40600290	BITUMINOUS MATERIALS (TACK COAT)	POUND	8,364	$	$
2.07	40600295	POLYMERIZED BITUMINOUS MATERIALS (TACK COAT)	POUND	8,364	$	$
2.08	40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	507	$	$
2.09	40603200	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-4.75, N50	TON	809	$	$
2.10	40604060	HOT-MIX ASPHALT SURFACE COURSE, IL-9.5, MIX "D", N50	TON	1,609	$	$
2.11	42001300	PROTECTIVE COAT	SQ YD	774	$	$
2.12	42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	168	$	$
2.13	42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	5,215	$	$
2.14	42400800	DETECTABLE WARNINGS	SQ FT	187	$	$
2.15	44000100	PAVEMENT REMOVAL	SQ YD	6,729	$	$
2.16	44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	18,289	$	$
2.17	44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	213	$	$
2.18	44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	897	$	$
2.19	44000600	SIDEWALK REMOVAL	SQ FT	5,435	$	$
2.20		CLASS D PATCHES, TYPE IV, 3 1/2 INCH	SQ YD	1,290	$	$
2.21	44201696	CLASS D PATCHES, TYPE IV, 4 INCH	SQ YD	587	$	$
2.22	44201723	CLASS D PATCHES, TYPE IV, 6 INCH	SQ YD	4,734	$	$
2.23		CLASS C PATCHES, SPECIAL, 6 INCH	SQ YD	11,034	$	$
2.24		CLASS C PATCHES, SPECIAL, 7 INCH	SQ YD	227	$	$

BID FORM - CHICAGO STREET COMBINATION SEWER SEPARATION PROJECT
BID 26-036

2.25		CLASS C PATCHES, SPECIAL, 12 INCH	SQ YD	847	$	$
2.26	78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	50	$	$
2.27	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	540	$	$
2.28	78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1,048	$	$
2.29	78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	186	$	$
2.30	78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	284	$	$
2.31	X6060048	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.18 (SPECIAL)	FOOT	938	$	$
2.32	X4021000	TEMPORARY ACCESS (PRIVATE ENTRANCE)	EACH	11	$	$
2.33	X4022000	TEMPORARY ACCESS (COMMERCIAL ENTRANCE)	EACH	3	$	$
2.34	X7800200	PAINT PAVEMENT MARKING CURB	FOOT	50	$	$
2.35	Z0004510	HOT-MIX ASPHALT DRIVEWAY PAVEMENT, 3"	SQ YD	53	$	$
2.36		SIDEWALK REMOVE AND RESET, BRICK	SQ FT	83	$	$
2.37		REMOVE AND RESET PAVER BRICK PAVEMENT	SQ YD	9	$	$
2.38		REMOVE AND REPLACE PCC CONCRETE RETAINING WALL	FOOT	49	$	$
2.39		TEMPORARY PATCHES (SPECIAL)	SQ YD	6,729	$	$
2.00		**Sub-Total**				**$**

		CODED PAY ITEMS				
3.00	**PAY ITEM #**	**WATERMAIN**	**UNITS**	**QUANTITY**	**UNIT COST**	**COST**
3.01	20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	67	$	$
3.02	56102900	DUCTILE IRON WATER MAIN 4"	FOOT	130	$	$
3.03	56103000	DUCTILE IRON WATER MAIN 6"	FOOT	163	$	$
3.04	56103100	DUCTILE IRON WATER MAIN 8"	FOOT	4,769	$	$
3.05	56103400	DUCTILE IRON WATER MAIN 16"	FOOT	50	$	$
3.06	56104800	WATER VALVES 4"	EACH	2	$	$
3.07	56104900	WATER VALVES 6"	EACH	2	$	$
3.08	56105000	WATER VALVES 8"	EACH	23	$	$
3.09	56105300	WATER VALVES 16"	EACH	1	$	$
3.10	56400500	FIRE HYDRANTS TO BE REMOVED	EACH	7	$	$
3.11	56400820	FIRE HYDRANT WITH AUXILIARY VALVE AND VALVE BOX	EACH	12	$	$
3.12	X0325003	VALVE AND VALVE VAULTS TO BE REMOVED	EACH	22	$	$
3.13		VALVE VAULTS, TYPE A, 4'-DIAMETER, WITH SPECIAL FRAME AND LID	EACH	26	$	$
3.14	X6026623	VALVE BOX	EACH	2	$	$
3.15	X5610656	WATER MAIN TO BE ABANDONED 6"	FOOT	3,758	$	$
3.16	X5610658	WATER MAIN TO BE ABANDONED 8"	FOOT	200	$	$
3.17	X5610716	WATER MAIN REMOVAL, 16"	FOOT	46	$	$
3.18	X5620116	WATER SERVICE CONNECTION (SHORT) (RESIDENTIAL)	EACH	24	$	$
3.19	X5620118	WATER SERVICE CONNECTION (LONG) (RESIDENTIAL)	EACH	18	$	$
3.20	X5620116	WATER SERVICE CONNECTION (SHORT) (RESIDENTIAL) WITH PAVEMENT REMOVAL	EACH	6	$	$
3.21	X5620118	WATER SERVICE CONNECTION (LONG) (RESIDENTIAL) WITH PAVEMENT REMOVAL	EACH	4	$	$
3.22	X5620118	WATER SERVICE CONNECTION (LONG) (COMMERCIAL)	EACH	4	$	$

BID FORM - CHICAGO STREET COMBINATION SEWER SEPARATION PROJECT
BID 26-036

3.23		WATER SERVICE CONNECTION (PRIVATE), TYPE K 1"	EACH	22	$	$
3.24		WATER SERVICE PIPE, TYPE L	FOOT	20	$	$
3.25	X5610746	WATER MAIN LINE STOP 6"	EACH	2	$	$
3.26	X5630004	CUT AND CAP EXISTING 4" WATER MAIN	EACH	4	$	$
3.27	X5630006	CUT AND CAP EXISTING 6" WATER MAIN	EACH	48	$	$
3.28	X5630008	CUT AND CAP EXISTING 8" WATER MAIN	EACH	9	$	$
3.29	X5630016	CUT AND CAP EXISTING 16" WATER MAIN	EACH	1	$	$
3.30	X5630704	CONNECTION TO EXISTING WATER MAIN 4"	EACH	3	$	$
3.31	X5630706	CONNECTION TO EXISTING WATER MAIN 6"	EACH	11	$	$
3.32	X5630708	CONNECTION TO EXISTING WATER MAIN 8"	EACH	5	$	$
3.33	X5630712	CONNECTION TO EXISTING WATER MAIN 12"	EACH	5	$	$
3.34	X5630716	CONNECTION TO EXISTING WATER MAIN 16"	EACH	6	$	$
3.35		SELECT GRANULAR BACKFILL (SPECIAL)	CU YD	67	$	$
3.36		TRENCH BACKFILL (SPECIAL)	CU YD	4,495	$	$
3.37		WATER MAIN LOWERING 8"	FOOT	25	$	$
3.38		WATER MAIN LOWERING 16"	FOOT	69	$	$
3.39		VALVE AND VALVE BOXES TO BE REMOVED	EACH	2	$	$
3.40		POINT-OF-USE WATER FILTER AND CARTRIDGES	EACH	22	$	$
3.00		**Sub-Total**				**$**

		CODED PAY ITEMS				
4.00	**PAY ITEM #**	**STORM SEWER**	**UNITS**	**QUANTITY**	**UNIT COST**	**COST**
4.01	20201200.00	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	90	$	$
4.02	550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	146	$	$
4.03	550A0070	STORM SEWERS, CLASS A, TYPE 1 15"	FOOT	62	$	$
4.04	550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	203	$	$
4.05	550A0360	STORM SEWERS, CLASS A, TYPE 2 15"	FOOT	308	$	$
4.06	550A0380	STORM SEWERS, CLASS A, TYPE 2 18"	FOOT	527	$	$
4.07	550A0410	STORM SEWERS, CLASS A, TYPE 2 24"	FOOT	28	$	$
4.08	550A0430	STORM SEWERS, CLASS A, TYPE 2 30"	FOOT	289	$	$
4.09	550A0450	STORM SEWERS, CLASS A, TYPE 2 36"	FOOT	452	$	$
4.10	550A0470	STORM SEWERS, CLASS A, TYPE 2 42"	FOOT	572	$	$
4.11	550A0480	STORM SEWERS, CLASS A, TYPE 2 48"	FOOT	744	$	$
4.12	550A0980	STORM SEWERS, CLASS A, TYPE 4 18"	FOOT	275	$	$
4.13	550A2340	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 1 18"	FOOT	22	$	$
4.14	550A2580	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 2 30"	FOOT	48	$	$
4.15	550A2610	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 2 42"	FOOT	39	$	$
4.16	550A2620	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 2 48"	FOOT	71	$	$
4.17	550B0130	STORM SEWERS, CLASS B, TYPE 1 27"	FOOT	6	$	$
4.18	550B0400	STORM SEWERS, CLASS B, TYPE 2 21"	FOOT	21	$	$
4.19	550B0420	STORM SEWERS, CLASS B, TYPE 2 27"	FOOT	8	$	$

BID FORM - CHICAGO STREET COMBINATION SEWER SEPARATION PROJECT
BID 26-036

4.20	55100200.00	STORM SEWER REMOVAL 6"	FOOT	113	$	$
4.21	55100300.00	STORM SEWER REMOVAL 8"	FOOT	313	$	$
4.22	55100400.00	STORM SEWER REMOVAL 10"	FOOT	12	$	$
4.23	55100500.00	STORM SEWER REMOVAL 12"	FOOT	12	$	$
4.24	55100700	STORM SEWER REMOVAL 15"	FOOT	27	$	$
4.25	55101100	STORM SEWER REMOVAL 21"	FOOT	17	$	$
4.26	60500050.00	REMOVING CATCH BASINS	EACH	29	$	$
4.27	60500060.00	REMOVING INLETS	EACH	12	$	$
4.28	X0323150	STORM SEWER TELEVISION INSPECTION, VIDEOTAPING, AND RECORDING	FOOT	4,595	$	$
4.29	X0323389	STORM SEWER CONNECTION	EACH	7	$	$
4.30	Z0056648	STORM SEWERS, TYPE 1, WATER MAIN QUALITY PIPE, 12", AWWA C900 DR 25	FOOT	113	$	$
4.31	Z0056668	STORM SEWERS, TYPE 2, WATER MAIN QUALITY PIPE, 12", AWWA C900 DR 25	FOOT	235	$	$
4.32	Z0056670	STORM SEWERS, TYPE 2, WATER MAIN QUALITY PIPE, 18", AWWA C900 DR 25	FOOT	166	$	$
4.33		STORM SEWERS, TYPE 2, WATER MAIN QUALITY PIPE, 20", AWWA C900 DR 25	FOOT	50	$	$
4.34	Z0056672	STORM SEWERS, TYPE 2, WATER MAIN QUALITY PIPE, 24", AWWA C900 DR 25	FOOT	210	$	$
4.35	X60207905	CATCH BASINS, SPECIAL, 2'-DIAMETER, WITH SPECIAL FRAME AND GRATE	EACH	21	$	$
4.36		CATCH BASINS, TYPE C, 2'-DIAMETER WITH SPECIAL FRAME AND LID	EACH	2	$	$
4.37		CATCH BASINS, SPECIAL, 3'-DIAMETER, WITH SPECIAL FRAME AND GRATE	EACH	20	$	$
4.38	X60218400	MANHOLES, TYPE A, 4'-DIAMETER, WITH SPECIAL FRAME AND GRATE	EACH	2	$	$
4.39	X60222000	MANHOLES, TYPE A, 4'-DIAMETER, WITH SPECIAL FRAME AND LID	EACH	20	$	$
4.40	X60221100	MANHOLES, TYPE A, 5'-DIAMETER, WITH SPECIAL FRAME AND LID	EACH	6	$	$
4.41	X60223800	MANHOLES, TYPE A, 6'-DIAMETER, WITH SPECIAL FRAME AND LID	EACH	4	$	$
4.42	X60224446	MANHOLES, TYPE A, 7'-DIAMETER, WITH SPECIAL FRAME AND LID	EACH	9	$	$
4.43	X60224459	MANHOLES, TYPE A, 8'-DIAMETER, WITH SPECIAL FRAME AND LID	EACH	1	$	$
4.44	X60224469	MANHOLES, TYPE A, 9'-DIAMETER, WITH SPECIAL FRAME AND LID	EACH	3	$	$
4.45		OVERFLOW STRUCTURE NO. 1	EACH	1	$	$
4.46		SELECT GRANULAR BACKFILL (SPECIAL)	CU YD	90	$	$
4.47		BACKFLOW PREVENTER, 24", SPECIAL	EACH	1	$	$
4.48		BACKFLOW PREVENTER, 27", SPECIAL	EACH	1	$	$
4.49		STORM SEWER TO BE ABANDONED 6"	FOOT	33	$	$
4.50		STORM SEWER TO BE ABANDONED 8"	FOOT	611	$	$
4.51		STORM SEWER TO BE ABANDONED 12"	FOOT	25	$	$
4.52		STORM SEWER TO BE ABANDONED 15"	FOOT	16	$	$
4.53		TRENCH BACKFILL (SPECIAL)	CU YD	5,904	$	$
4.00		**Sub-Total**				**$**

		CODED PAY ITEMS				
5.00	**PAY ITEM #**	**SANITARY SEWER**	**UNITS**	**QUANTITY**	**UNIT COST**	**COST**
5.01	20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	30	$	$
5.02	X0323577	SANITARY SEWER TELEVISION INSPECTION, VIDEOTAPING AND RECORDING	FOOT	198	$	$
5.03	X0324585	SANITARY SEWER SERVICE REMOVAL AND REPLACEMENT	EACH	33	$	$

BID FORM - CHICAGO STREET COMBINATION SEWER SEPARATION PROJECT
BID 26-036

5.04	X0324878	ADJUSTING SANITARY SEWER SERVICE LINE	EACH	33	$	$
5.05	X0326713	SANITARY SEWER CONNECTION	EACH	9	$	$
5.06		SELECT GRANULAR BACKFILL (SPECIAL)	CU YD	30	$	$
5.07		SANITARY SEWER, PVC (D3034) SDR 26, 10"	FOOT	21	$	$
5.08		SANITARY SEWER, PVC (D3034) SDR 26, 12"	FOOT	93	$	$
5.09		SANITARY SEWER, PVC (D3034) SDR 26, 24"	FOOT	59	$	$
5.10		SANITARY SEWER, PVC (D3034) SDR 26, 36"	FOOT	25	$	$
5.11		MANHOLES, SANITARY, 4'-DIAMETER, WITH SPECIAL FRAME AND LID	EACH	3	$	$
5.12		MANHOLES, SANITARY, 5'-DIAMETER, WITH SPECIAL FRAME AND LID	EACH	1	$	$
5.13		MANHOLES, SANITARY, 6'-DIAMETER, WITH SPECIAL FRAME AND LID	EACH	3	$	$
5.14		DROP SANITARY MANHOLES, 4'-DIAMETER, WITH SPECIAL FRAME AND LID	EACH	2	$	$
5.15		OVERFLOW STRUCTURE NO. 2	EACH	1	$	$
5.16	X6026050	SANITARY MANHOLES TO BE ADJUSTED	EACH	26	$	$
5.17	X6026052	SANITARY MANHOLES FRAME AND ADJUSTMENT SEALING	EACH	26	$	$
5.18		MANHOLE REHABILITATION – MULTILAYER SYSTEM, 4' DIAMETER	FOOT	239	$	$
5.19		MANHOLE REHABILITATION – MULTILAYER SYSTEM, 5' DIAMETER	FOOT	22	$	$
5.20		REPLACEMENT MANHOLE BENCH, 4' DIAMETER	EACH	24	$	$
5.21		REPLACEMENT MANHOLE BENCH, 5' DIAMETER	EACH	2	$	$
5.22		SANITARY SEWER SPOT REPAIR 10"	FOOT	25	$	$
5.23		SANITARY SEWER SPOT REPAIR 12"	FOOT	15	$	$
5.24		SANITARY SEWER SPOT REPAIR 36"	FOOT	5	$	$
5.25		REPLACE SANITARY SERVICE CONNECTION TO MAIN	EACH	20	$	$
5.26		CASING AROUND CLEANOUT IN PAVEMENT	EACH	32	$	$
5.27		TRENCH BACKFILL (SPECIAL)	CU YD	437	$	$
5.28		SANITARY SEWER, SPECIAL, 24"	FOOT	23	$	$
5.00		**Sub-Total**				**$**

		CODED PAY ITEMS				
6.00	**PAY ITEM #**	**MISCELLANEOUS**	**UNITS**	**QUANTITY**	**UNIT COST**	**COST**
6.01	66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	100	$	$
6.02	67100100	MOBILIZATION	L SUM	1	$	$
6.03		TRAFFIC CONTROL AND PROTECTION (SPECIAL)	L SUM	1	$	$
6.04	X2130010	EXPLORATION TRENCH, SPECIAL	FOOT	200	$	$
6.05	X0325675	TEMPORARY PAVEMENT RAMPS FOR DRAINAGE AND UTILITY CASTINGS	EACH	97	$	$
6.06	Z0013798	CONSTRUCTION LAYOUT	L SUM	1	$	$
6.07	XXXXXX15	MISCELLANEOUS ADDITIONS AT THE CITY'S DIRECTION	UNITS	1	$	$
6.00		**Sub-Total**				**$**

		CODED PAY ITEMS				
7.00	**PAY ITEM #**	**SEWER LINING**	**UNITS**	**QUANTITY**	**UNIT COST**	**COST**
7.01	X0322785	PRE-CONSTRUCTION CLEANING AND TELEVISING	FOOT	5,380	$	$
7.02	X5430208	CURED-IN-PLACE PIPE LINER, 8"	FOOT	755	$	$
7.03	X5430210	CURED-IN-PLACE PIPE LINER, 10"	FOOT	585	$	$

BID FORM - CHICAGO STREET COMBINATION SEWER SEPARATION PROJECT
BID 26-036

7.04	X5430212	CURED-IN-PLACE PIPE LINER, 12"	FOOT	1,165	$	$
7.05	X5430230	CURED-IN-PLACE PIPE LINER, 30"	FOOT	330	$	$
7.06	X5430236	CURED-IN-PLACE PIPE LINER, 36"	FOOT	2,545	$	$
7.07	X03266XA	CURED-IN-PLACE PIPE LINER, 6" (SANITARY SEWER SERVICE LATERAL)	EACH	93	$	$
7.00		**Sub-Total**				**$**

BASE BASE BID SUMMARY			
1.00		**EARTHWORK & EROSION CONTROL**	**$**
2.00		**PAVEMENT**	**$**
3.00		**WATERMAIN**	**$**
4.00		**STORM SEWER**	**$**
5.00		**SANITARY SEWER**	**$**
6.00		**MISCELLANEOUS**	**$**
7.00		**SEWER LINING**	**$**
BASE BID TOTAL COST			**$**

BASE BID TOTAL COST IN WORDS _____

The City of Elgin reserves the right to award the contract to the lowest responsible Bidder for the BASE BID TOTAL COST, whichever is deemed to be in the best interest of the City of Elgin at the City's sole discretion. Each Bidder must submit bids for the BASE BID to be eligible for the award of the contract.