Statement of work/ Specifications

CORONADO GY26 RANGE FENCE MATERIALS PURCHASE
NOGALES, SIERRA VISTA, SANTA CATALINA, AND SAFFORD RANGER DISTRICTS
CORONADO NATIONAL FOREST
MAY 26, 2026

Prepared by:
Chrissy Pearson – Rangeland Management Specialist
Coronado Range GY26 Fence Materials Purchase
NOGALES, SIERRA VISTA, SAFFORD, AND SANTA CATALINA RANGER DISTRICTS
CORONADO NATIONAL FOREST

Scope of Work

General Work Location

Supply and deliver the fence materials to the district addresses above. **Call at least 48 hours** prior to delivery to be sure someone is available to receive the shipment.

Time Limit

The vendor will have (4) four weeks to complete this task from issuance of the contract.

----- **End Scope of Work** -------

Specifications and Drawings

ASTM Certified
T-Post, (T-133) 5.5ft, w/ 4 clips/post
Smooth Wire, 12.5 gauge, Class 1 (1320 ft. per roll)
Barbed Wire, 12.5 gauge, 2pt, 4 inch barb spacing, Class 1, (1320 ft per roll)
Wire Stays, 42in, 9.5 gauge, Class 1, (100 stays per bundle)
Brace Angle Iron Post (2.5 in X 2.5 in. X 1/4 in. X 7ft)
Angle Iron Braces (2 in. X 2 in. X 1/4 in. X 7 ft)
Nuts & Bolts, 1/2 in. X 1.5 in.

----- **End Specifications and Drawings** -------