

Campus Terrace

SCHEDULE OF FINISHES

Foundation Excavations and foundation walling to comply with the minimum requirements of the NHBRC AGREED

1 FOUNDATION

- | | | |
|----------------|--|---|
| Stairs/Columns | | <ul style="list-style-type: none"> Reinforced concrete foundation to Professional Engineer's design and details. Termite poisoning to floor of staircase and columns |
| Walls/Columns | | <ul style="list-style-type: none"> Clay stock brickwork to be plastered and painted Concrete columns to be painted Basement paving to Architect's detail |
| Sundries | | <ul style="list-style-type: none"> Parking bays to be demarcated and numbered with road marking paint. Steel frame with Wood automated pedestrian and sliding motor gate to Architect's detail. |

2 SUPER STRUCTURE

- | | | |
|-------------------|---------------------------------|--|
| Walls | | <ul style="list-style-type: none"> Clay stock brickwork to be plastered and painted. |
| Concrete slab | | <ul style="list-style-type: none"> Reinforced concrete slab to Professional Engineers design and details. |
| Window frames | | <ul style="list-style-type: none"> Aluminium - Colour charcoal |
| Door frames | Block entrance
Unit entrance | <ul style="list-style-type: none"> Aluminium - Colour charcoal Timber frame (Meranti) |
| Window sills | Internal
External | <ul style="list-style-type: none"> Plaster and paint Brick on edge to be plastered and painted |
| External finishes | | <ul style="list-style-type: none"> Plastered and finished with one coat plaster primer and two coats Dulux Wheatherguard Colours to Architect's schedule |
| External soffits | | <ul style="list-style-type: none"> Plastered and finished with one coat plaster primer and two coats Dulux Wheatherguard Colours to Architect's schedule |

3 ROOF

- | | | |
|------------|--|--|
| Roof slabs | | <ul style="list-style-type: none"> Reinforced concrete slabs to Professional Engineers design and details. Torch-on waterproofing applied by Specialist to manufacturers full specs. |
|------------|--|--|

4 INTERNAL FINISHES

General wall finishes		<ul style="list-style-type: none"> • Smooth Plaster finished with one coat plaster primer and two coats Dulux Dura 65 Acrylic PVA paint • Window sills to be plastered and painted as for wall.
Bathroom wall finishes		<ul style="list-style-type: none"> • Smooth Plaster finished with one coat plaster primer and two coats Dulux Pearl glo • Ceramic tiles in shower to the height of shower frame • Mosaic tiles to shower floor • Mosaic splash back the width of the basin • 90cm high tiled skirting to match floor tile.
Kitchen wall finishes		<ul style="list-style-type: none"> • Smooth Plaster finished with one coat plaster primer and two coats Dulux Dura 65 Acrylic PVA paint
Ceilings		<ul style="list-style-type: none"> • Concrete slabs ceiling to be plastered and finished with one coat plaster primer and two coats white Dulux Nucote PVA • Provide ruled joint at junction of wall to slab
	Bathroom	<ul style="list-style-type: none"> • Finished with one coat plaster primer and two coats Dulux Pearl glo
Floor tiles		<ul style="list-style-type: none"> • Ceramic Tiles 500mm x 500mm • All tiles laid to a square pattern
Shower Floor		<ul style="list-style-type: none"> • Mosaic tiles to shower floor
Skirting		<ul style="list-style-type: none"> • 90mm high plain Meranti skirting finished with three coats Wooddoc Wood sealer.
Front door		<ul style="list-style-type: none"> • Solid Meranti door • Door and frame finished with three coats Wooddoc wood sealer • Four lever door lock • Stainless steel door handle
Internal door	Bathroom	<ul style="list-style-type: none"> • Hollow core surface sliding door finished with one undercoat and two coats white gloss Enamel paint • Bucket handle
Balcony doors		<ul style="list-style-type: none"> • Aluminium - Colour charcoal & glass

5 SANITARY WARE

Kitchen

- Square 450 x 385 x 165 stainless steel basin
- Hans Grohe Cosmo E2 Basin Mixer

Bathroom

- "Macneil" Nova Slimline Basin 750mm - Colour white
- Hans Grohe Cosmo E2 Basin Mixer
- "Isca" shower arm 400mm & Veritas shower rose 200mm x 200mm
- Hans Grohe Cosmo E2 Shower Mixer

WC

- "Macneil" Bermuda close coupled toilet - Colour white

Bathroom Accessories

- Paper holder for WC
- Single towel rail
- Shower soap holder

6 GEYSER

- 1000L horizontal tank (geyser) on the roof in conjunction with a 19kW air source heat pump Per block

7 FITTINGS

Kitchen cupboards & worktops

- Worktops: Pro Quartz Speckle
- White melamine cupboard carcasses
- WASHED-SHALE-ALPINE-MELAMINE Edging, Side panels and Doors
- Kick plates -150mm Aluminium
- Stainless Steel Bar handles
- Layout as per detailed drawings

Vanity unit

- White melamine cupboard carcasses
- WASHED-SHALE-ALPINE-MELAMINE edging, side panels and doors
- Stainless Steel Bar handles
- Layout as per detailed drawings

Build in cupboards

- White melamine cupboard carcasses
- WASHED-SHALE-ALPINE-MELAMINE Edging, Side panels and Doors
- Layout as per detailed drawings
- Stainless Steel Bar handles

Kitchen hob

- Defy 2 plate solid hob stainless steel

- Curtain tracks and mirrors by purchaser.

Curtain tracks and Mirrors

8 ELECTRICAL WORKS

Electrical work

- All units to be fitted with pre-paid electrical meters
- One Light point in Kitchen, Bathroom, Living Area and Bedroom(one-bedroom apartment only)
- Light fittings (see attached pictures)
- Power Points Kitchen - 1 Double 1 Single
- Power Points Living area - 1 Double 1 Single
- Power Points Sleeping area (bachelor only) – 1 Double
- Power Points Bedroom (one-bedroom only) - 2 Single

9 EXTERNAL WORK

Access security

- Motorized gate
- Intercom connected to each individual unit
- Electric fence 6 lines

Refuse area

- Refuse area is located as per Architects layout

Landscaping

- Landscaping as per Landscape Architects drawings

Balustrades

- 1 meter high Balustrades as per Architects detail

Parking

- Undercover parking bays allocated as per Architects schedule

Central satellite TV

- Reticulation for satellite TV to be provided (decoders not included)
- TV point - 1

Data Point

- Conduits and draw wires will be provided in units
- Data point - 1

Boundary wall

- Clay brick Walls/Columns to be plastered and painted with ClearVu fencing as per Architect detail