

CHECKERS POOL Standard OPENING Includes the Following:

- Removal of 1 winter cover. Power wash and clean cover with environmentally safe cleaner preserver (this ensures the longest life of cover). Neatly fold and place cover in storage bag when available. Place cover and other items “next to” pool, shed or garage.
- Bucket wash off pool deck around pool.
- Remove all plugs, reinstall directionals, skimmer baskets, auto cleaner wall fitting.
- Install ladders, rails and dive-board when applicable. Components of these items will be inspected for safety prior to installation. This is to prevent physical harm or pool structure damage. (Any faulty parts or components will be replaced at an additional cost.)
- Start-up of 1 pump, 1 filter, and up to 4 accessories.
- Perform “on-site” water analysis. Apply start-up chemicals (when requested). Balancing chemicals will be applied if needed after “on-site” water analysis and billed at completion of service as well as DE applied for charge of filter with media when applicable.
- Inspect entire system for proper operation. Additional equipment parts needed for proper pool operation will be billed separately (ie. gauges, o-rings, etc.)
- Attempt to fire pool heater when applicable. (Faulty parts or cleaning may be performed at the opening, or may require a separate service call at an additional cost.)
- Leave homeowner with copy of checklist and special instructions.

RESPONIBILITIES REQUIRED OF SWIMMING POOL OWNER FOR POOL OPENING:

- WATER MUST BE AT PROPER LEVEL IN POOL PRIOR TO POOL OPENING. PLACE GARDEN HOSE UNDER COVER AND FILL POOL TO APPROXIMATELY 6” FROM TOP OF POOL. IF A RETURN TRIP IS REQUIRED TO START SYSTEM THERE WILL BE A MINIMUM ADDITIONAL CHARGE OF \$85.00.
- POOL ACCESSORIES AND EQUIPMENT MUST BE READILY AVAILABLE FOR TECHNICIANS AT TIME OF SERVICE.
- POOL TIMER AND OR POWER TO FILTER SYSTEM MUST BE ON PRIOR TO CHECKERS ARRIVAL.
- HAVE ACCESS TO POOL AREA AND EQUIPMENT. GATES OPEN AND UNLOCKED.
- HAVE POOL COVER DRAINED OF EXCESS WATER AND DEBRIS. **\$70 PER ½ HOUR IF WE HAVE TO.**
- **LET US KNOW WHAT YOU WILL NEED FOR AN ENJOYABLE SEASON!**

CHECKERS POOL Standard CLOSING Includes the Following: Removal of rails and ladders, dive-board (optional). Remove fittings from returns, skimmers, etc. Remove auto cleaner, wall fitting and remove debris from filter bag. Backwash pool filter, remove time clock pegs when available. Drain and professionally winterize entire plumbing system, filter(s) pump(s) heater(s). De-water and winterize all underground plumbing. CHECKERS POOL USES HIGH VOLUME GAS POWERED AIR COMPRESSORS TO EFFECTIVELY WINTERIZE ALL UNDERGROUND PLUMBING INCLUDING BOTTOM DRAINS. *We do not use hand held electric blowers as do most others, they are not effective for long hydraulic runs to bottom drains and other pool components.* Plug all in-pool components and install skimmer winter ice expander plugs. Any plugs needed will be provided by Checkers Pool (additional cost) if homeowner does not supply or if found to be inadequate for proper winterization. Apply the necessary winter chemicals to pool at (additional cost if applicable). Properly install homeowner’s winter cover, (any needed parts, water tubes, anchors, etc., will be installed at an additional cost.) Install homeowners cover pump when applicable. Place all items “next to” pool, shed or garage. Leave homeowner with copy of checklist and special instructions.

Checkers Pool will at our discretion, apply additional winter chemicals to pool if water is in an extremely unsatisfactory condition at time of closing. Install winter chemical feeder for Mesh type covers. (Checkers will install at additional cost if homeowner does not supply.) This is a one-time charge for the feeder which is reusable. Feeder will be filled with homeowner tablets or supplied by Checkers Pool.

RESPONIBILITIES REQUIRED OF SWIMMING POOL OWNER for POOL CLOSING:

- WATER MUST BE AT PROPER LEVEL IN POOL PRIOR TO POOL CLOSING. Concrete pools should be just below tile.
- POOL ACCESSORIES AND EQUIPMENT MUST BE READILY AVAILABLE FOR TECHNICIANS AT TIME OF SERVICE.
- POOL TIMER AND OR POWER TO FILTER SYSTEM MUST BE ON PRIOR TO TECHNICIANS ARRIVAL.
- HAVE ACCESS TO POOL AREA AND EQUIPMENT. GATES OPEN AND UNLOCKED.
- HAVE THE POOL IN THE CONDITION YOU WOULD LIKE IT CLOSED. We do not vacuum at closing unless previously scheduled.

CHECKERS POOL WILL DELIVER AT TIME OF OPENING MAINTENANCE EQUIPMENT OR CHEMICALS FOR YOUR POOL. YOU WILL RECEIVE OUR SPECIAL PRE-SEASON SALES PRICING DISCOUNTS. A SAVINGS OF AT LEAST 20% OFF OUR ALREADY LOW PRICES.

Requested Items to be Delivered at Pool Opening

- | | | | | | |
|--|---------------------------------------|--|--|--|-----------------------------------|
| <input type="checkbox"/> TEST KIT | <input type="checkbox"/> WALL BRUSH | <input type="checkbox"/> LEAF NET | <input type="checkbox"/> VACUUM HOSE | <input type="checkbox"/> VACUUM HEAD | <input type="checkbox"/> TELEPOLE |
| <input type="checkbox"/> SAFETY ROPE | <input type="checkbox"/> THERMOMETER | <input type="checkbox"/> BACKWASH HOSE | <input type="checkbox"/> SKIMMER VAC PLATE | <input type="checkbox"/> TILE CLEANER | <input type="checkbox"/> SHOCK |
| <input type="checkbox"/> ALGAECIDE | <input type="checkbox"/> BACTERIACIDE | <input type="checkbox"/> CLARIFIER | <input type="checkbox"/> PH BALANCE | <input type="checkbox"/> ALKALINITY CONTROL | |
| <input type="checkbox"/> CALCIUM BALANCE | <input type="checkbox"/> DE POWDER | <input type="checkbox"/> CHLORINE TABS | <input type="checkbox"/> SCUM LINE PREVENTER | <input type="checkbox"/> METAL/STAIN CONTROL | |